

# PERMUTATION PATTERNS, STANLEY SYMMETRIC FUNCTIONS AND GENERALIZED SPECHT MODULES

SARA BILLEY AND BRENDAN PAWLOWSKI

**ABSTRACT.** Generalizing the notion of a vexillary permutation, we introduce a filtration of  $S_\infty$  by the number of Schur function terms in the Stanley symmetric function, with the  $k$ th filtration level called the  $k$ -vexillary permutations. We show that for each  $k$ , the  $k$ -vexillary permutations are characterized by avoiding a finite set of patterns. A key step is the construction of a Specht series, in the sense of James and Peel, for the Specht module associated to the diagram of a permutation. As a corollary, we prove a conjecture of Liu on diagram varieties for certain classes of permutation diagrams related to 3-vexillary permutations. We apply similar techniques to characterize multiplicity-free Stanley symmetric functions, as well as permutations whose diagram is equivalent to a forest in the sense of Liu.

## 1. INTRODUCTION

In [30], Stanley defined a symmetric function  $F_w$  depending on a permutation  $w$ , with the property that the coefficient of  $x_1 \cdots x_\ell$  in  $F_w$  is the number of reduced words of  $w$ . Therefore, if  $F_w = \sum_\lambda a_{w\lambda} s_\lambda$  is written in terms of Schur functions, then

$$|\text{Red}(w)| = \sum_\lambda a_{w\lambda} f^\lambda, \quad (1)$$

where  $f^\lambda$  is the number of standard Young tableaux of shape  $\lambda$  and  $\text{Red}(w)$  the set of reduced words of  $w$ .

Edelman and Greene [6] gave an algorithm which realizes (1) bijectively and shows that the  $a_{w\lambda}$  are nonnegative. An alternative approach can be given in terms of the nil-plactic monoid [16].

**Theorem.** *Given a permutation  $w$ , there is a set  $\mathcal{EG}(w)$  of semistandard Young tableaux and a bijection*

$$\text{Red}(w) \leftrightarrow \{(P, Q) : P \in \mathcal{EG}(w), Q \text{ a standard tableau of shape } \text{shape}(P)\}.$$

The tableaux  $\mathcal{EG}(w)$  are those semistandard tableaux whose column word—obtained by reading up columns starting with the leftmost—is a reduced word for  $w$ . The (transposed) shapes of these tableaux precisely give the Schur function expansion of  $F_w$ :

$$F_w = \sum_{P \in \mathcal{EG}(w)} s_{\text{shape}(P)^t},$$

where  $\lambda^t$  is the conjugate of  $\lambda$ . Define the permutation statistic  $EG(w) = \sum a_{w\lambda} = |\mathcal{EG}(w)|$ , which we call the *Edelman-Greene number*.

---

*Date:* May 1, 2013.

Both authors were partially supported by grant DMS-1101017 from the NSF.

Stanley also characterized those  $w$  for which  $F_w$  is a single Schur function, or equivalently for which  $EG(w) = 1$ : these are the *vexillary* permutations, those avoiding the pattern 2143. Our main results can be viewed as generalizations of this characterization. The first main theorem shows that  $\mathcal{EG}(w)$  is well-behaved with respect to pattern containment.

**Theorem 1.1.** *Let  $v, w$  be permutations with  $w$  containing  $v$  as a pattern. There is an injection  $\iota : \mathcal{EG}(v) \hookrightarrow \mathcal{EG}(w)$  such that if  $P \in \mathcal{EG}(v)$ , then  $\text{shape}(P) \subseteq \text{shape}(\iota(P))$ . Moreover, if  $P, P'$  have the same shape, so do  $\iota(P), \iota(P')$ .*

Let  $S_\infty = \bigcup_{n \geq 0} S_n$ . An immediate corollary is that the sets  $\{w \in S_\infty : EG(w) \leq k\}$  respect pattern containment, in the sense that if  $EG(w) \leq k$  and  $w$  contains  $v$ , then  $EG(v) \leq k$ . Our second main result is a sort of converse.

**Definition 1.2.** Given a positive integer  $k$ , a permutation  $w \in S_n$  is  *$k$ -vexillary* if  $EG(w) \leq k$ .

For example, the 1-vexillary permutations are the vexillary permutations. More information about these permutations and their enumeration can be found in the Online Encyclopedia of Integer Sequences (OEIS) entry A005802. The number of  $k$ -vexillary permutations in  $S_n$  for  $k = 2, 3, 4$  appear in the OEIS as A224318, A223034, A223905.

Like the vexillary permutations, the  $k$ -vexillary permutations can be characterized by permutation patterns. This is our first main theorem.

**Theorem 1.3.** *For each integer  $k \geq 1$ , there is a finite set  $V_k$  of permutations such that  $w$  is  $k$ -vexillary if and only if  $w$  avoids all patterns in  $V_k$ .*

For the 2-vexillary and 3-vexillary permutations, we have explicitly identified the list of patterns characterizing these sets. We use these properties to prove a conjecture of Ricky Liu on diagram varieties related to 3-vexillary permutation diagrams. We note that permutation diagrams correspond with forests in the sense of Liu if and only if the permutation avoids 4 patterns. Furthermore, we can give a nice description of Fulton's essential set for 3-vexillary permutations.

Schur positive expansions of symmetric functions which are multiplicity free have been important in many cases related to representation theory and algebraic geometry. For example, the Pieri rule for multiplying a Schur function times a Schur function with just one row or column is multiplicity free. More generally, Stembridge addressed the question of when the product of two Schur functions have a multiplicity free expansion [31]. Thomas and Yong refined this work further in [33].

As a corollary of Theorem 1.1, we show that the multiplicity free Stanley symmetric functions are indexed by a set of permutations closed under taking patterns. We conjecture that these multiplicity free permutations can be characterized by avoiding a finite set of permutations in  $S_6 \cup \dots \cup S_{11}$ . As with  $k$ -vexillary permutations, one can define a filtration on permutations by bounding the multiplicities in the Stanley symmetric functions. It is shown that each filtration level again respects pattern containment. These permutations are also related to a new type of pattern on the code of a permutation. We also note that 3-vexillary permutations are multiplicity free.

In Section 2, we recall the connection between Stanley symmetric functions and the representation theory of the symmetric group, along with the Lascoux-Schützenberger recurrence for computing Stanley symmetric functions. We also recall the definitions of pattern avoidance and containment. In Section 3, we introduce the notion of a James-Peel tree for a general diagram following [12], and prove a new decomposition theorem for general Specht modules based on Pieri's rule. Section 4 specializes these ideas to permutation diagrams, with the Lascoux-Schützenberger tree as a key tool, and we prove Theorem 1.1. In Section 5, we analyze in more detail the relationship between  $EG(w)$  and  $EG(v)$  for  $v$  a pattern in  $w$ , and prove Theorem 1.3. Section 6 gives an application of Theorem 1.1 to computing the cohomology class of certain subvarieties of Grassmannians related to a conjecture of Ricky Liu. In Section 7, the multiplicity free and multiplicity bounded permutations are discussed. Section 8 is devoted to open problems.

## 2. BACKGROUND

**2.1. Permutation patterns.** We first recall the definitions of pattern avoidance and containment for permutations.

**Definition 2.1.** Let  $x = x(1) \cdots x(n)$  be a sequence of distinct integers. The *flatten map*  $fl$  is defined by letting  $fl(x)$  be the unique  $v \in S_n$  such that  $x(i) < x(j)$  if and only if  $v(i) < v(j)$ .

**Definition 2.2.** A permutation  $w$  *contains* a permutation  $v$  if there are  $i_1 < \cdots < i_k$  such that  $fl(w(i_1) \cdots w(i_k)) = v$ . If  $w$  does not contain  $v$ , then  $w$  *avoids*  $v$ . Frequently we call the smaller permutation  $v$  a *pattern* which  $w$  contains or avoids.

**Example 2.3.** The permutation 2513764 contains the patterns 2143 (e.g. as the subsequence 2174) and 23154. It avoids 1234.

**2.2. Specht modules.** Our proof of Theorem 1.1 goes via the representation theory of  $S_n$ , specifically the interpretation of  $F_w$  as the Frobenius characteristic of a certain *generalized Specht module*, which we discuss next. We assume the reader is familiar with the classical  $S_n$  representation theory described beautifully in [29].

**Definition 2.4.** A *diagram* is a finite subset of  $\mathbb{N} \times \mathbb{N}$ .

We refer to the elements of a diagram as *cells*. The diagrams of greatest interest for us will be *permutation diagrams* (sometimes called Rothe diagrams, from [28]). Given  $w \in S_n$ , define

$$D(w) = \{(i, w(j)) : 1 \leq i < j \leq n, w(i) > w(j)\}.$$

We'll draw  $D(w)$  using matrix coordinates:

$$D(243165) = \begin{array}{cccccc} \circ & \times & \cdot & \cdot & \cdot & \cdot \\ \circ & \cdot & \circ & \times & \cdot & \cdot \\ \circ & \cdot & \times & \cdot & \cdot & \cdot \\ \times & \cdot & \cdot & \cdot & \cdot & \cdot \\ \cdot & \cdot & \cdot & \cdot & \circ & \times \\ \cdot & \cdot & \cdot & \cdot & \times & \cdot \end{array}$$

Members of a diagram will be represented by  $\circ$ . We'll often augment  $D(w)$  by adding  $\times$  at the points  $(i, w(i))$ . By definition, no member of the diagram lies below or to the right of an  $\times$ .

A *filling* of a diagram  $D$  is a bijection  $T : D \rightarrow \{1, \dots, n\}$ , where  $n = |D|$ . There is a natural left action of  $S_n$  on fillings of  $D$  by permuting entries. The *row group*  $\mathbf{R}(T)$  of a filling  $T$  is the subgroup of  $S_n$  consisting of permutations  $\sigma$  which act on  $T$  by permuting entries within their row; the *column group*  $\mathbf{C}(T)$  is defined analogously. Define the *Young symmetrizer* of a filling  $T$  by

$$y_T = \sum_{p \in \mathbf{R}(T)} \sum_{q \in \mathbf{C}(T)} \text{sgn}(q) qp, \quad (2)$$

an element of  $\mathbb{C}[S_n]$ .

**Definition 2.5.** Given a diagram  $D$  and a choice of filling  $T$ , the *Specht module*  $S^D$  is the  $S_n$ -module  $\mathbb{C}[S_n]y_T$ , where  $n = |D|$ . The *Schur function*  $s_D$  of  $D$  is the Frobenius characteristic of  $S^D$ .

**Remark 2.6.** This definition generalizes the familiar definitions when  $D$  is the Ferrers diagram of a partition. For general  $D$ , there is no known expression  $s_D = \sum_T x^T$  with  $T$  running over some nice set of fillings of  $D$ . When  $D$  is a permutation diagram, [8] shows that the set of *balanced labellings* of  $D$  works, but we will not need this fact.

Replacing  $T$  with a different filling amounts to conjugating  $\mathbf{R}(T)$ ,  $\mathbf{C}(T)$ , and  $y_T$ , so the isomorphism type of  $S^D$  is independent of the choice of  $T$ . Reordering the rows and columns of  $D$  also leads to an isomorphic Specht module, so we make the following definition.

**Definition 2.7.** If a diagram  $D$  is obtained from a diagram  $D'$  by permuting rows and columns, say  $D$  and  $D'$  are *equivalent*, and write  $D \simeq D'$ . This includes inserting or deleting empty rows and columns.

A partition  $\lambda = (\lambda_1 \geq \dots \geq \lambda_\ell \geq 1)$  has an associated diagram

$$\{(i, j) : 1 \leq i \leq \ell, 1 \leq j \leq \lambda_i\},$$

its *Ferrers diagram*, which we will also denote by  $\lambda$ . Over  $\mathbb{C}$ , the Specht modules of Ferrers diagrams form complete sets of irreducible  $S_n$ -representations. For more on these classical irreducible Specht modules, see [11] or [29]. In general, it is an open problem to find a reasonable combinatorial algorithm for decomposing  $S^D$  into irreducibles. Reiner and Shimozono do so in [26] for *percent-avoiding* diagrams  $D$ : those with the property that if  $(i_1, j_1), (i_2, j_2) \in D$  with  $i_1 > i_2, j_1 < j_2$ , then one of  $(i_1, j_2)$  and  $(i_2, j_1)$  is in  $D$ . This includes the class of skew shapes and permutation diagrams. In a different direction, Liu [19] decomposes  $S^D$  when  $D$  is a diagram corresponding in a certain sense to a forest.

**2.3. Stanley symmetric functions.** Every permutation  $w$  can be written as a product of adjacent transpositions  $s_i = (i, i+1)$ . Let  $\ell(w)$  be the minimal length of any such product. Let  $\text{Red}(w)$  be the collection of *reduced words* for  $w$ . Thus if  $a = (a_1, a_2, \dots, a_{\ell(w)}) \in \text{Red}(w)$  then  $s_{a_1} s_{a_2} \dots s_{a_{\ell(w)}} = w$  and this is a minimal length expression for  $w$ .

Given a reduced word  $a \in \text{Red}(w)$ , let  $I(a)$  be the set of integer sequences  $1 \leq i_1 \leq \dots \leq i_{\ell(w)}$  such that if  $a_j < a_{j+1}$ , then  $i_j < i_{j+1}$ .

**Definition 2.8.** The *Stanley symmetric function* of  $w$  is<sup>1</sup>

$$F_w = \sum_{a \in \text{Red}(w)} \sum_{i \in I(a)} x_{i_1} \cdots x_{i_{\ell(w)}}.$$

It is shown in [30] that  $F_w$  is indeed symmetric. For a permutation  $w$ , let  $1^m \times w = 12 \cdots m(w(1) + m)(w(2) + m) \cdots$ . The results of [2] show that  $F_w = \lim_{m \rightarrow \infty} \mathfrak{S}_{1^m \times w}$ , where  $\mathfrak{S}_v$  is a Schubert polynomial as defined by Lascoux and Schützenberger in [17]. The same result can also be seen by decomposing a Schubert polynomial into key polynomials using the nilplactic monoid [16]. This implies  $F_w = F_{1^m \times w}$  for all  $m \geq 1$ . Theorem 31 in [24] and Theorem 20 in [26] then imply the following result, which is also implicit in [14].

**Theorem 2.9.** For any permutation  $w$ ,  $F_w = s_{D(w)}$ .

Stanley symmetric functions can be decomposed into Schur functions using a recursion introduced in [15, 17]. Given a permutation  $w$ , let  $r$  be maximal with  $w(r) > w(r+1)$ . Then let  $s > r$  be maximal with  $w(s) < w(r)$ . Let  $t_{ij}$  denote the transposition  $(ij)$ , and define

$$T(w) = \{wt_{rs}t_{rj} : \ell(wt_{rs}t_{rj}) = \ell(w) \text{ for some } j\};$$

or, if the set on the right-hand side is empty, set  $T(w) = T(1 \times w)$ . The members of  $T(w)$  are called *transitions* of  $w$ . The *Lascoux-Schützenberger tree* (L-S tree for short) is the finite rooted tree of permutations with root  $w$  where the children of a vertex  $v$  are:

- None, if  $v$  is vexillary (avoids 2143).
- $T(v)$  otherwise.

The finiteness of this tree is not immediately obvious [15], see Remark 5.16 for a short proof. More on the Lascoux-Schützenberger tree and its relationship to Schubert polynomials and Stanley symmetric functions can be found in [23].

Monk's rule for Schubert polynomials and the identity  $F_w = \lim_{m \rightarrow \infty} \mathfrak{S}_{1^m \times w}$  lead to the recurrence

$$F_w = \sum_{v \in T(w)} F_v. \quad (3)$$

This, together with the finiteness of the Lascoux-Schützenberger tree terminating in vexillary leaves, and the fact that  $F_v$  is a Schur function exactly when  $v$  is vexillary, imply that

$$F_w = s_{D(w)} = \sum_v s_{\text{shape}(v)},$$

where  $v$  runs over the leaves of the L-S tree, and  $\text{shape}(v)$  denotes the partition whose shape is equivalent to  $D(v)$ . Here we use the fact that  $D(v)$  is equivalent to a partition diagram if and only if  $v$  is vexillary [21].


Note that upon taking coefficients of  $x_1 x_2 \cdots x_\ell$  in the transition recurrence (3), one obtains  $|\text{Red}(w)| = \sum_{v \in T(w)} |\text{Red}(v)|$ . Little [18] gives a bijective proof of this equality.

**Remark 2.10.** The reduced words of  $1 \times w$  are exactly those of  $w$  with all letters shifted up by 1, and it is known that the same is true of the tableaux in  $\mathcal{EG}(1 \times w)$  compared to the tableaux in  $\mathcal{EG}(w)$  since the algorithm only depends on the relative

<sup>1</sup>Stanley's original function  $G_w$  is our  $F_{w^{-1}}$ .

sizes of the letters in the reduced words [6]. In particular, the multiset of shapes are the same and  $F_w = F_{1 \times w}$ . Since the L-S tree is finite, there is some  $m$  such that in constructing the tree for  $1^m \times w$ , we never need to make the replacement of  $v$  by  $1 \times v$ . Thus we will ignore this possible step in what follows.

**Example 2.11.** The Lascoux-Schützenberger tree of 321465 is



### 3. JAMES-PEEL MOVES AND SUBDIAGRAMS

Let  $D$  be a diagram. Given two positive integers  $a, b$ , let  $R_{a \rightarrow b}D$  be the diagram which contains a cell  $(i, j)$  if and only if one of the following cases holds:

- $i \neq a, b$  and  $(i, j) \in D$ .
- $i = b$  and either  $(a, j) \in D$  or  $(b, j) \in D$ .
- $i = a$  and both  $(a, j), (b, j) \in D$ .

That is,  $R_{a \rightarrow b}D$  is obtained by moving cells in row  $a$  to row  $b$  if the appropriate position is empty. Similarly, we define  $C_{c \rightarrow d}D$  by moving cells of  $D$  in column  $c$  to column  $d$  if possible. For example,

$$D = \begin{array}{cccc} \cdot & \circ & \cdot & \circ \\ \cdot & \cdot & \circ & \circ \end{array} \quad R_{2 \rightarrow 1}D = \begin{array}{cccc} \cdot & \circ & \circ & \circ \\ \cdot & \cdot & \cdot & \circ \end{array}$$

We also define  $R_{a \rightarrow b}T$  and  $C_{c \rightarrow d}T$  for a filling  $T$ , in the same way. From here through the proof of Theorem 3.5, we always view  $S^D$ ,  $S^{R_{a \rightarrow b}D}$ ,  $S^{C_{c \rightarrow d}D}$  as the specific left ideals in  $\mathbb{C}[S_{|D|}]$  generated by  $y_T$ ,  $y_{R_{a \rightarrow b}T}$ ,  $y_{C_{c \rightarrow d}T}$  for a fixed filling  $T$  of  $D$  following the notation in Section 2.

We'll call the operators  $R_{a \rightarrow b}$  and  $C_{c \rightarrow d}$  *James-Peel moves*, thanks to this theorem due to James and Peel.

**Theorem 3.1.** [12, Theorem 2.4] *Let  $(i_1, j_1), (i_2, j_2) \in D$  be such that  $(i_1, j_2), (i_2, j_1) \notin D$ . Let  $D_R = R_{i_1 \rightarrow i_2}D$  and  $D_C = C_{j_1 \rightarrow j_2}D$ . Then there is a surjective homomorphism  $\phi : S^D \twoheadrightarrow S^{D_R}$  with  $S^{D_C} \subseteq \ker \phi$ .*

We prove a generalization of this statement, and for the proof we will need more explicit knowledge of the homomorphism  $\phi$ . Given  $(i_1, j_1), (i_2, j_2)$  as in Theorem 3.1, write  $T_R = R_{i_1 \rightarrow i_2}T$  and  $T_C = C_{j_1 \rightarrow j_2}T$ . Let  $Y$  and  $Z$  be sets of coset representatives in  $\mathbf{C}(T_R)$  and  $\mathbf{R}(T_C)$  respectively such that

$$\mathbf{C}(T_C) = Y(\mathbf{C}(T_C) \cap \mathbf{C}(T))$$

$$\mathbf{R}(T_R) = (\mathbf{R}(T_R) \cap \mathbf{R}(T))Z.$$

Then Theorem 3.1 follows from the identities using the Young symmetrizers (2)

$$(a) \quad y_T \sum_{\pi \in Z} \pi = y_{T_R}$$

$$(b) \sum_{\pi \in Y} \text{sgn}(\pi) \pi \cdot y_T = y_{T_C}$$

$$(c) y_{T_C} \sum_{\pi \in Z} \pi = 0.$$

Thus we can take  $\phi$  in Theorem 3.1 to be right multiplication by  $\sum_{\pi \in Z} \pi$ .

**Remark 3.2.** Only (c) above depends on the existence of a pair of cells  $(i_1, j_1), (i_2, j_2)$  as in Theorem 3.1. For arbitrary  $a, b, c, d$  we still get a surjection  $S^D \twoheadrightarrow S^{R_{a \rightarrow b} D}$  from (a), and a containment  $S^{C_{c \rightarrow d} D} \subseteq S^D$  from (b). Over  $\mathbb{C}$ , we also get an inclusion  $S^{R_{a \rightarrow b} D} \hookrightarrow S^D$ .

**Lemma 3.3.** Suppose  $R_{a \rightarrow b} C_{c \rightarrow d} D = C_{c \rightarrow d} R_{a \rightarrow b} D$ . Let

$$\begin{aligned} \phi : S^D &\twoheadrightarrow S^{R_{a \rightarrow b} D} \\ \phi' : S^{C_{c \rightarrow d} D} &\twoheadrightarrow S^{R_{a \rightarrow b} C_{c \rightarrow d} D} \end{aligned}$$

be the surjections constructed above. Then

$$\phi' = \phi|_{S^{C_{c \rightarrow d} D}}.$$

*Proof.* Fix a filling  $T$  of  $D$  and take sets of coset representatives  $Z, Z'$  with

$$\begin{aligned} \mathbf{R}(T) &= (\mathbf{R}(R_{a \rightarrow b} T) \cap \mathbf{R}(T))Z \\ \mathbf{R}(C_{c \rightarrow d} T) &= (\mathbf{R}(R_{a \rightarrow b} C_{c \rightarrow d} T) \cap \mathbf{R}(C_{c \rightarrow d} T))Z', \end{aligned}$$

so that  $\phi, \phi'$  are right multiplication by  $\sum_{\pi \in Z} \pi$  and  $\sum_{\pi \in Z'} \pi$  respectively.

Applying a move  $C_{c \rightarrow d}$  to a filling does not affect its row group, so

$$\begin{aligned} \mathbf{R}(T) &= \mathbf{R}(C_{c \rightarrow d} T) = (\mathbf{R}(R_{a \rightarrow b} C_{c \rightarrow d} T) \cap \mathbf{R}(T))Z' \\ &= (\mathbf{R}(C_{c \rightarrow d} R_{a \rightarrow b} T) \cap \mathbf{R}(T))Z' \\ &= (\mathbf{R}(R_{a \rightarrow b} T) \cap \mathbf{R}(T))Z'. \end{aligned}$$

Thus we can take  $Z' = Z$ . □

**Definition 3.4.** A subset  $D'$  of a diagram  $D$  is a *subdiagram* if it is the intersection of some rows and columns with  $D$ . That is, there are sets  $U, V \subseteq \mathbb{N}$  such that  $D' = (U \times V) \cap D$ .

Given two diagrams  $D_1, D_2$  with  $D_1 \subseteq [r] \times [c]$ , let

$$D_1 \cdot D_2 = D_1 \cup \{(i + r, j + c) : (i, j) \in D_2\}.$$

In this language, Theorem 3.1 applies when we have  $(1) \cdot (1)$  as a subdiagram in  $D$ . Our generalization of the James-Peel Lemma applies to a subdiagram of the form  $(p - 1, p - 2, \dots, 1) \cdot (1)$ . To simplify indexing, we will assume without loss of generality that our subdiagram occurs in rows  $1, \dots, p$  and columns  $1, \dots, p$ . Write  $\delta_p$  for the staircase shape  $(p - 1, p - 2, \dots, 1)$ .

**Theorem 3.5.** Suppose  $D$  contains  $\delta_p \cdot (1)$  as a subdiagram in rows  $1, \dots, p$  and columns  $1, \dots, p$ . There is a filtration

$$0 = M_0 \subseteq M_1 \subseteq \dots \subseteq M_p = S^D$$

of  $S^D$  by  $S_{|D|}$ -submodules such that for each  $1 \leq j \leq p$ , there is a surjection

$$M_j / M_{j-1} \twoheadrightarrow S^{R_{p \rightarrow p-j+1} C_{p \rightarrow j} D}.$$

*Proof.* Let  $F_j = C_{p \rightarrow j}D$  and  $G_j = R_{p \rightarrow p-j+1}C_{p \rightarrow j}D$ . Set

$$M_j = \sum_{i=1}^j S^{F_j} \subseteq S^D.$$

Consider, for each  $j$ , the two surjections

$$\begin{aligned} \phi_j : S^D &\twoheadrightarrow S^{R_{p \rightarrow p-j+1}D} \\ \theta_j : S^{F_j} &\twoheadrightarrow S^{G_j} \end{aligned}$$

given by Theorem 3.1. We have  $R_{p \rightarrow p-j+1}C_{p \rightarrow j}D = C_{p \rightarrow j}R_{p \rightarrow p-j+1}D$ . Indeed, this commutation property depends only on the subdiagram of  $D$  in rows  $p-j+1, p$  and columns  $j, p$ . By hypothesis this subdiagram is

$$\begin{array}{cc} \cdot & \cdot \\ \cdot & \circ \end{array}$$

and either order of James-Peel moves results in the subdiagram

$$\begin{array}{ccc} \circ & \cdot & \\ \cdot & \cdot & \cdot \end{array}$$

Therefore, Lemma 3.3 says that  $\theta_j = \phi_j|_{S^{F_j}}$ .

If  $1 \leq i < j$ , then  $(i, p-j+1), (p, p) \in D$  and  $(i, p), (p, p-j+1) \notin D$ , so Theorem 3.1 implies that  $S^{F_i} \subseteq \ker \phi_j$ , hence  $M_{j-1} \subseteq \ker \phi_j$ . Thus,  $S^{F_j} \cap M_{j-1} \subseteq S^{F_j} \cap \ker \phi_j = \ker \theta_j$ , so  $\theta_j$  descends to a surjection

$$S^{F_j} / (S^{F_j} \cap M_{j-1}) \twoheadrightarrow S^{G_j}.$$

Since there is a canonical isomorphism

$$M_j / M_{j-1} \simeq S^{F_j} / (S^{F_j} \cap M_{j-1})$$

given by  $m + M_{j-1} \mapsto m + S^{F_j} \cap M_{j-1}$  where  $m \in S^{F_j}$ , we are done.  $\square$

**Remark 3.6.** Theorem 3.1 and hence Theorem 3.5 are actually valid over any field, and lead to the existence of *Specht series* for certain Specht modules. A *Specht series* for an  $S_n$ -module  $M$  is a filtration  $0 = M_0 \subseteq M_1 \subseteq \cdots \subseteq M_N = M$  where each quotient  $M_{i+1}/M_i$  is isomorphic to a (classical) Specht module  $S^\lambda$ . Over  $\mathbb{C}$  these are just composition series, but in general they are coarser, since Specht modules are indecomposable but not necessarily irreducible in finite characteristic.

We won't need this level of generality, so from now on we will work over  $\mathbb{C}$  and freely split exact sequences. In particular,

**Corollary 3.7.** *If  $D$  contains  $\delta_p \cdot (1)$  as a subdiagram in rows  $1, \dots, p$  and columns  $1, \dots, p$ , then we have the inclusion*

$$\bigoplus_{j=1}^p S^{R_{p \rightarrow p-j+1}C_{p \rightarrow j}D} \hookrightarrow S^D \quad (4)$$

as  $S_{|D|}$ -modules over  $\mathbb{C}$ .

Observe that  $C_{j \rightarrow j}D = R_{j \rightarrow j}D = D$  for all  $j$  and  $D$ , so for  $j = 1$  and  $j = p$  above only one move changes the diagram.



**Example 3.8.** Take

$$D = D(4261735) = \begin{array}{cccccc} & \circ & \circ & \circ & \cdot & \cdot \\ & \circ & \cdot & \cdot & \cdot & \cdot \\ \circ & \cdot & \circ & \cdot & \circ & \\ \cdot & \cdot & \cdot & \cdot & \cdot & \\ \cdot & \cdot & \circ & \cdot & \circ & \end{array}$$

where we have omitted the last empty rows and columns. The subdiagram in rows 1, 2, 5 and columns 1, 2, 5 is  $(2, 1) \cdot (1)$ . The following diagrams appear in (4):

$$\begin{array}{ccccc} \circ & \circ & \circ & \cdot & \circ & & \circ & \circ & \circ & \cdot & \cdot \\ \circ & \cdot & \cdot & \cdot & \cdot & & \circ & \circ & \circ & & \\ R_{5 \rightarrow 1} D = \circ & \cdot & \circ & \cdot & \circ & & \circ & \circ & \circ & & \\ \cdot & \cdot & \cdot & \cdot & \cdot & & \circ & \circ & \circ & & \\ \cdot & \cdot & \circ & \cdot & \cdot & & \circ & \cdot & \circ & \cdot & \circ \\ & & & & & & \circ & \cdot & \circ & \cdot & \cdot \end{array}$$

Corollary 3.7 now says  $S^{(3,3,3)} \oplus S^{R_{5 \rightarrow 1} D} \oplus S^{C_{5 \rightarrow 1} D} \hookrightarrow S^{D(w)}$ . Applying Theorem 3.1 to the cells  $(2, 1)$ ,  $(5, 3)$  in  $R_{5 \rightarrow 1} D$  gives  $S^{(4,3,2)} \oplus S^{(4,3,1,1)} \hookrightarrow S^{R_{5 \rightarrow 1} D}$ . Using the cells  $(1, 2)$ ,  $(3, 5)$  in  $C_{5 \rightarrow 1} D$ , Theorem 3.1 gives  $S^{(4,2,2,1)} \oplus S^{(3,3,2,1)} \hookrightarrow S^{C_{5 \rightarrow 1} D}$ . In fact, all these inclusions are isomorphisms

$$S^{D(w)} \simeq S^{(3,3,3)} \oplus S^{(4,3,2)} \oplus S^{(4,3,1,1)} \oplus S^{(4,2,2,1)} \oplus S^{(3,3,2,1)},$$

as one can check using the Lascoux-Schützenberger tree, or by computing the Edelman-Greene tableaux of 4261735:

$$\begin{array}{|c|c|c|} \hline 1 & 2 & 3 \\ \hline 2 & 4 & 5 \\ \hline 3 & 5 & 6 \\ \hline \end{array} \quad \begin{array}{|c|c|c|} \hline 1 & 2 & 3 \\ \hline 2 & 4 & 5 \\ \hline 3 & 6 & \\ \hline 5 & & \\ \hline \end{array} \quad \begin{array}{|c|c|c|c|} \hline 1 & 2 & 3 & 5 \\ \hline 2 & 4 & & \\ \hline 3 & 6 & & \\ \hline 5 & & & \\ \hline \end{array} \quad \begin{array}{|c|c|c|c|} \hline 1 & 2 & 3 & 5 \\ \hline 2 & 4 & 6 & \\ \hline 3 & & & \\ \hline 5 & & & \\ \hline \end{array} \quad \begin{array}{|c|c|c|c|} \hline 1 & 2 & 3 & 5 \\ \hline 2 & 4 & 6 & \\ \hline 3 & 5 & & \\ \hline & & & \\ \hline \end{array}.$$

This example also provides a case where Theorem 3.5 is more powerful than Theorem 3.1. For reasons which will become clear in Section 4, we would like to apply James-Peel moves which apply to the cell  $(5, 5)$ , as the first stage of moves above do. There are 3 possible cells one could pair  $(5, 5)$  with in Theorem 3.1:  $(1, 1)$ ,  $(1, 2)$ , and  $(2, 1)$ . However, one finds that in each case that the inclusion  $S^{C_{c \rightarrow d} D} \oplus S^{R_{a \rightarrow b} D} \hookrightarrow S^D$  is not an isomorphism, so  $S^D$  cannot be completely decomposed using such moves.

Note that when Corollary 3.7 is applied to the diagram  $\delta_p \cdot (1)$  itself, the resulting partitions are exactly those arising from applying Pieri's rule to expand  $s_{\delta_p} s_{(1)}$  in terms of Schur functions. Indeed, it follows readily from the group algebra definitions that  $S^{D_1 \cdot D_2} \simeq \text{Ind}_{S_{|D_1|} \times S_{|D_2|}}^{|D_1|+|D_2|} S^{D_1} \otimes S^{D_2}$ , and hence that  $s_{D_1 \cdot D_2} = s_{D_1} s_{D_2}$ . We can therefore view Corollary 3.7 as applying Pieri's rule to a subdiagram of  $D$ . See the discussion surrounding Example 3.17 for an expansion on this idea.

**Definition 3.9.** Given a diagram  $D$  contained in  $[m] \times [n]$ , define

$$\begin{aligned} D^{\max} &= (R_{m \rightarrow 1} \cdots R_{2 \rightarrow 1})(R_{m \rightarrow 2} \cdots R_{3 \rightarrow 2}) \cdots (R_{m \rightarrow m-1}) D \\ D^{\min} &= (C_{n \rightarrow 1} \cdots C_{2 \rightarrow 1})(C_{n \rightarrow 2} \cdots C_{3 \rightarrow 2}) \cdots (C_{n \rightarrow n-1}) D. \end{aligned}$$

These diagrams are both equivalent to partitions—an identification we will freely make—and satisfy  $S^{D^{\max}}, S^{D^{\min}} \hookrightarrow S^D$  by Remark 3.2. To be precise,  $D^{\min}$  is the partition gotten by sorting the row lengths of  $D$ , and  $D^{\max}$  is the conjugate of the

partition gotten by sorting the column lengths. This second description implies the following lemma.

**Lemma 3.10.** *If  $\mathbf{I}$  is any sequence of James-Peel row moves  $R_{a \rightarrow b}$ , then  $D^{\max} = (\mathbf{I}D)^{\max}$ . Likewise, if  $\mathbf{J}$  is a sequence of column moves  $C_{c \rightarrow d}$ , then  $D^{\min} = (\mathbf{J}D)^{\min}$ .*

The partitions  $D^{\min}$  and  $D^{\max}$  play a special role in the structure of  $S^D$ . In the case  $D = D(w)$ , the next lemma is Theorem 4.1 from [30].

**Lemma 3.11.** *Let  $D$  be any diagram. If  $S^\lambda \hookrightarrow S^D$ , then  $D^{\min} \leq \lambda \leq D^{\max}$  in dominance. Also,  $S^{D^{\min}}$  and  $S^{D^{\max}}$  appear in  $S^D$  with multiplicity one.*

*Proof.* We will prove the part of the statement referring to  $D^{\min}$ , with the proof for  $D^{\max}$  being analogous. Induct on  $\ell(D^{\min})$ , the number of non-empty rows of  $D$ . The lemma is obvious when  $D$  is a single row. Let  $H$  be a row of  $D$  with minimal length, and set  $E = D \setminus H$ . Then  $D$  is the image of  $E \cdot H$  under James-Peel moves—push  $H$  to its original row, then each cell individually to its original column—so  $S^D \hookrightarrow S^{E \cdot H}$ .

Suppose  $S^\mu \hookrightarrow S^D \hookrightarrow S^{E \cdot H}$ . Since  $s_{E \cdot H} = s_E s_H$ , Pieri's rule says  $\mu$  is obtained from some  $\lambda$  with  $S^\lambda \hookrightarrow S^E$  by adding  $|H|$  cells to it, no two in the same column. By construction,  $D^{\min}$  is obtained by appending a row of length  $|H|$  to  $E^{\min}$ . The induction hypothesis gives  $E^{\min} \leq \lambda$ . To show  $D^{\min} \leq \mu$ , let  $\alpha, \beta$  be the partitions equivalent to  $D^{\min}$  and  $E^{\min}$ . Observe that for all  $1 \leq m \leq \ell(E^{\min})$ ,

$$\sum_{i=1}^m \alpha_i = \sum_{i=1}^m \beta_i \leq \sum_{i=1}^m \lambda_i \leq \sum_{i=1}^m \mu_i, \quad (5)$$

while if  $m = \ell(E^{\min}) + 1 = \ell(D^{\min})$ , both sides of (5) are equal to  $|D|$ , since  $\ell(\mu) \leq \ell(\lambda) + 1 \leq \ell(E^{\min}) + 1$ .

By induction,  $S^{E^{\min}}$  appears with multiplicity one in  $S^E$ . Since Pieri's rule is multiplicity free,  $S^{D^{\min}}$  appears with multiplicity one in  $S^{E \cdot H}$ , hence with multiplicity at most one in  $S^D$ . Furthermore,  $S^{D^{\min}}$  does actually appear in  $S^D$ , because  $D^{\min}$  is the image of  $D$  under James-Peel moves, and so it appears with multiplicity one.  $\square$

James-Peel moves and Corollary 3.7 present one possible way to decompose a Specht module into irreducibles. In general it is not known if an arbitrary Specht module can be decomposed by finding some appropriate tree of James-Peel moves, as the inclusion in Corollary 3.7 may not be an isomorphism. The way we prove Theorem 1.1 is to find such a decomposition for the case of  $D(w)$ . The usefulness of James-Peel moves for us comes from the fact that they are well-behaved with respect to subdiagram inclusion, and pattern inclusion for permutations corresponds to subdiagram inclusion on the level of permutation diagrams.

To be more precise about this, we make the following definition.

**Definition 3.12.** A *James-Peel tree* for a diagram  $D$  is a rooted tree  $\mathcal{T}$  with vertices labeled by diagrams and edges labeled by sequences of James-Peel moves, satisfying the following conditions:

- The root of  $\mathcal{T}$  is  $D$ .
- If  $B$  is a child of  $A$  with a sequence  $\mathbf{JP}$  of James-Peel moves labeling the edge  $A \rightarrow B$ , then  $B = \mathbf{JP}(A)$ .

- If  $A$  has more than one child, these children arise as a result of applying Corollary 3.7 to  $A$ . That is,  $A$  contains  $\delta_p \cdot (1)$  as a subdiagram in rows  $i_1 < \dots < i_p$  and columns  $j_1 < \dots < j_p$ , and each edge leading down from  $A$  is labeled  $R_{i_p \rightarrow i_{p-k+1}} C_{j_p \rightarrow j_k}$  for some distinct values  $1 \leq k \leq p$  (perhaps not all such  $k$  appear).

Note that the vertex labels are completely determined by the root and the edge labels. When a vertex is labeled by a permutation diagram  $D(w)$ , sometimes we will refer to it simply as  $w$ . See Examples 3.17 and 3.20 later in this section for examples of James-Peel trees.

Corollary 3.7 and Remark 3.2 immediately imply the following lemma.

**Lemma 3.13.** *If  $D$  has a James-Peel tree  $\mathcal{T}$  with leaves  $A_1, \dots, A_m$ , then  $\bigoplus_i S^{A_i} \hookrightarrow S^D$  as  $S_{|D|}$ -modules over  $\mathbb{C}$ .*

**Definition 3.14.** A James-Peel tree  $\mathcal{T}$  for  $D$  is *complete* if its leaves  $A_1, \dots, A_m$  are equivalent to Ferrers diagrams of partitions and  $S^D \simeq \bigoplus_i S^{A_i}$ .

In [12], an algorithm is given which constructs a complete James-Peel tree when  $D$  is a skew shape. More generally, Reiner and Shimozono [25] construct a complete James-Peel tree for any *column-convex* diagram: a diagram  $D$  for which  $(a, x), (b, x) \in D$  with  $a < b$  implies  $(i, x) \in D$  for all  $a < i < b$ . In the next section we construct a complete James-Peel tree for the diagram of a permutation, so it's worth noting that neither of these classes of diagrams contains the other. For example,  $D(37154826)$  is not equivalent to any column-convex or row-convex diagram, while the column-convex diagram

$$\begin{array}{cccc} \circ & \circ & \cdot & \cdot \\ \circ & \cdot & \circ & \cdot \\ \circ & \cdot & \cdot & \circ \end{array}$$

is not equivalent to the diagram of any permutation. The James-Peel trees constructed in [12] and [25] are binary trees based on moves from Theorem 3.1. By Corollary 3.7, the James-Peel trees constructed here do not need to be binary, a vertex can have an arbitrary number of children.

**Remark 3.15.** Theorem 3.5 shows that a complete James-Peel tree for  $D$  yields a Specht series for  $S^D$  over any field. In particular, Theorem 4.2 below shows that  $S^{D(w)}$  always has a Specht series.

**Definition 3.16.** Given a James-Peel tree  $\mathcal{T}'$  for a subdiagram  $D'$  of  $D$ , the *induced* James-Peel tree  $\mathcal{T}$  for  $D$  is defined as follows. Start with  $\mathcal{T}$  an unlabeled tree isomorphic to  $\mathcal{T}'$ , with  $\phi : \mathcal{T}' \rightarrow \mathcal{T}$  an isomorphism. Give each edge  $\phi(A_1) - \phi(A_2)$  of  $\mathcal{T}$  the same label as the edge  $A_1 - A_2$  of  $\mathcal{T}'$ . Label the root  $\phi(D')$  of  $\mathcal{T}$  with  $D$ , and label the rest of the vertices according to the James-Peel moves labeling the edges in  $\mathcal{T}$ .

Observe that the first two conditions of Definition 3.12 clearly hold for  $\mathcal{T}$  as constructed. The subdiagram of  $D'$  needed in the third condition for  $\mathcal{T}'$  and  $D'$  works just as well for  $\mathcal{T}$  and  $D$ , when viewed as a subdiagram of  $D$ . Thus,  $\mathcal{T}$  is a James-Peel tree for  $D$ .

The notion of an induced James-Peel tree provides a convenient way to discuss a generalization of Theorem 3.5 from the case of a subdiagram  $\delta_p \cdot (1)$  to that of

any subdiagram  $\lambda \cdot (k)$  with  $\lambda$  a partition. Recall the classical *Pieri rule*:


$$s_\lambda s_{(k)} = \sum_{\mu} s_\mu,$$

where  $\mu$  runs over all partitions gotten by adding  $k$  cells to  $\lambda$ , no two in the same column. That is, let  $\text{hstrips}_k(\lambda)$  be the set of length  $\ell(\lambda) + 1$  compositions  $\alpha$  of  $k$  such that  $\alpha_i \leq \lambda_i - \lambda_{i-1}$  for  $i > 1$ . Then  $s_\lambda s_{(k)} = \sum_{\alpha \in \text{hstrips}_k(\lambda)} s_{\lambda + \alpha}$ , where  $\lambda + \alpha$  is entrywise addition.

The moves in Theorem 3.5 can be thought of as realizing Pieri's rule on  $\delta_p \cdot (1)$  in terms of James-Peel moves. Suppose we have a James-Peel tree  $\mathcal{T}$  for  $\lambda \cdot (k)$  whose leaves are the partitions  $\lambda + \alpha$  for  $\alpha \in \text{hstrips}_k(\lambda)$ . If  $D$  contains  $\lambda \cdot (k)$  as a subdiagram, we can take the James-Peel tree for  $D$  induced by  $\mathcal{T}$ , which amounts to realizing Pieri's rule on the subdiagram  $\lambda \cdot (k)$  using James-Peel moves, generalizing Theorem 3.5.

In fact we only need the case  $\lambda = \delta_p$ ,  $k = 1$ , so rather than state and prove a precise theorem, we will be content with giving an example of such a tree.

**Example 3.17.** Take  $\lambda = (3, 1, 1)$ ,  $k = 2$ . In each non-leaf vertex, we have shaded the cells to which Theorem 3.5 is being applied.



The main example of induced James-Peel trees for us will come from permutation patterns. The connection is that if  $w$  contains a pattern  $v$ , then  $D(v)$  is (up to reindexing) a subdiagram of  $D(w)$ . Specifically, if the pattern  $v$  appears in positions  $i_1, \dots, i_k$  of  $w$ , then  $D(v)$  is the subdiagram of  $D(w)$  induced by the rows  $i_1, \dots, i_k$  and columns  $w(i_1), \dots, w(i_k)$ .

Let  $M(D)$  denote the multiset of partitions of  $n = |D|$  such that  $S^D \simeq \bigoplus_{\lambda \in M(D)} S^\lambda$ . Given partitions  $\lambda, \mu$ , let  $\lambda + \mu$  be the partition  $(\lambda_1 + \mu_1, \lambda_2 + \mu_2, \dots)$ , padding  $\lambda$  or  $\mu$  with 0's as necessary. Let  $\lambda \cup \mu$  be the partition whose parts are the (multiset) union of the parts of  $\lambda$  and those of  $\mu$ .

**Lemma 3.18.** *Suppose  $D_1, D_2$  are subdiagrams of  $D$ , each with a complete James-Peel tree, and such that  $D_1 = (U \times V) \cap D$  and  $D_2 = (U^c \times V^c) \cap D$ . Let  $F_1 = (U^c \times V) \cap D$  and  $F_2 = (U \times V^c) \cap D$ . Then there is a well-defined injection  $\iota : M(D_1) \times M(D_2) \rightarrow M(D)$  given by*

$$\iota(\lambda, \mu) = (\lambda \cup F_1^{\min}) + (F_2^{\max} \cup \mu).$$

*Proof.* Without loss of generality we can assume  $U = \{1, 2, \dots, i\}$  and  $V = \{1, 2, \dots, j\}$  by permuting rows and columns of  $D$  if necessary. Let  $\mathcal{T}_1, \mathcal{T}_2$  be complete James-Peel trees for  $D_1, D_2$ . Then, we can further assume that the leaves of  $\mathcal{T}_1, \mathcal{T}_2$  are all partition diagrams by doing extra James-Peel moves to sort the rows and columns.

Let  $\mathcal{T}$  be the James-Peel tree for  $D$  induced from  $\mathcal{T}_1$ , with  $\phi : \mathcal{T}_1 \rightarrow \mathcal{T}$  an isomorphism as in Definition 3.16. Since  $D$  contains  $D_1 = \phi^{-1}(D)$  as a subdiagram, each vertex  $A$  of  $\mathcal{T}$  contains  $\phi^{-1}(A)$  as a subdiagram. In particular, each leaf  $B$  of  $\mathcal{T}$  has the block form

$$B = \begin{array}{|c|c|} \hline \lambda & F'_2 \\ \hline F'_1 & D_2 \\ \hline \end{array}, \quad (6)$$

where  $\lambda$  is the shape of  $\phi^{-1}(B)$ ,  $F'_1$  is the image of  $F_1$  under moves  $C_{c \rightarrow d}$ , and  $F'_2$  the image of  $F_2$  under moves  $R_{a \rightarrow b}$ .

Using the block form (6), we next add a single child to each leaf  $B$  of  $\mathcal{T}$ . By Lemma 3.10,  $(F'_1)^{\min} = (F_1)^{\min}$  and  $(F'_2)^{\max} = (F_2)^{\max}$ . Thus, there is a sequence  $\mathbf{I}_B$  of upward row moves involving only rows in  $U$ , and a sequence  $\mathbf{J}_B$  of leftward column moves involving only columns in  $V$ , such that  $\mathbf{J}_B(F'_1) = F_1^{\min}$  and  $\mathbf{I}_B(F'_2) = F_2^{\max}$ . Since the upper-left block is a partition diagram, it is unaffected by the James-Peel moves  $\mathbf{I}_B$  and  $\mathbf{J}_B$ . Since no cell of  $D_2$  lies in a row in  $U$  or a column in  $V$ ,  $\mathbf{J}_B$  and  $\mathbf{I}_B$  do not change  $D_2$  either. Thus, we can define

$$\tilde{B} = \mathbf{I}_B \mathbf{J}_B(B) = \begin{array}{|c|c|} \hline \lambda & F_2^{\max} \\ \hline F_1^{\min} & D_2 \\ \hline \end{array}.$$

To each leaf  $B$  of  $\mathcal{T}$ , attach the child  $\tilde{B}$  via an edge labeled  $\mathbf{I}_B \mathbf{J}_B$ . Note, the result is still a James-Peel tree for  $D$ . We will abuse notation and again call this tree  $\mathcal{T}$ .

We modify  $\mathcal{T}$  one more time by augmenting each leaf with an induced tree for  $D_2$ . Specifically, to each leaf  $\tilde{B}$  of  $\mathcal{T}$ , attach the James-Peel tree for  $\tilde{B}$  induced by  $\mathcal{T}_2$ . As above, each leaf  $C$  of the new tree descending from  $\tilde{B}$  now has block form

$$C = \begin{array}{|c|c|} \hline \lambda & F_2'' \\ \hline F_1'' & \mu \\ \hline \end{array}, \quad (7)$$

where  $\lambda, \mu$  are a pair of shapes in  $M(D_1) \times M(D_2)$ ,  $F_1''$  is the result of applying row moves to  $F_1^{\min}$  and  $F_2''$  is the result of applying column moves to  $F_2^{\max}$ . Notice that the upper-right and lower-left block of  $\tilde{B}$  and  $C$  are equivalent, since both are equivalent to partitions. The upper-left block of  $\tilde{B}$  and  $C$  are exactly the same since the induced tree for  $\tilde{B}$  does not touch the first  $i$  rows and  $j$  columns. Again, we abuse notation by calling this tree  $\mathcal{T}$ .

Finally, we modify  $\mathcal{T}$  once again so the leaves all have block form with 4 partition shapes. Assume  $C$  is a descendant of  $\tilde{B}$  with block diagonal shapes  $\lambda, \mu$  as in (7) above. Let  $\mathbf{I}_C$  be the sequence of upward James-Peel row moves needed to sort the rows of  $F_1''$  into the partition shape  $F_1^{\min}$ , and let  $\mathbf{J}_C$  be the sequence of leftward column moves needed to sort the columns of  $F_2''$  into the partition shape  $F_2^{\max}$ . Note, such moves will not change the shapes  $\lambda$  and  $\mu$  when applied to  $C$  since they are partitions. Thus, one can define

$$\tilde{C} := \mathbf{I}_C \mathbf{J}_C(C) = \begin{array}{|c|c|} \hline \lambda & F_2^{\max} \\ \hline F_1^{\min} & \mu \\ \hline \end{array}, \quad (8)$$

with all four subdiagrams equal to honest left- and top-justified Ferrers diagrams. For each leaf  $C$  of  $\mathcal{T}$ , attach  $\tilde{C} = \mathbf{I}_C \mathbf{J}_C(C)$  as a child.

Observe that the resulting tree  $\mathcal{T}$  is a James-Peel tree for  $D$ , and the leaves are in bijection with the multiset  $M(D_1) \times M(D_2)$ . One can also see that if a leaf  $\tilde{C}$  of  $\mathcal{T}$  has diagonal shapes  $\lambda, \mu$  then

$$\tilde{C}^{\max} = (\lambda \cup F_1^{\min}) + (F_2^{\max} \cup \mu).$$

and the shape of  $\tilde{C}^{\max}$  only depends on  $\lambda, \mu, F_1, F_2$  and not on  $B$  or  $C$ . Thus, we define  $\iota(\lambda, \mu)$  to be the partition of shape  $\tilde{C}^{\max}$  which is in  $M(D)$  by Lemma 3.11 and Lemma 3.13. This gives a well-defined injection of multisets  $\iota : M(D_1) \times M(D_2) \rightarrow M(D)$  as intended.  $\square$

For the most part we will only need a simpler version of this lemma.

**Corollary 3.19.** *Suppose  $D$  has a subdiagram  $D'$  with a complete James-Peel tree. There is an injection  $\iota : M(D') \hookrightarrow M(D)$  such that  $\lambda \subseteq \iota(\lambda)$ . Moreover,  $\iota(\lambda)$  depends only on  $\lambda$ : if  $\lambda$  appears  $k$  times in  $M(D')$ , then  $\iota(\lambda)$  appears at least  $k$  times in  $M(D)$ .*

In particular, taking  $D = D(w)$  and  $D' = D(v)$  for  $v$  a pattern in  $w$ , Corollary 3.19 together with the equalities

$$s_{D(w)} = F_w = \sum_{P \in \mathcal{EG}(w)} s_{\text{shape}(P)} t$$


will immediately imply Theorem 1.1 once we show that  $D(w)$  always has a complete James-Peel tree.

**Example 3.20.** Take the diagram  $D = D(316524)$ . Rows 5, 6 and column 6 are empty, so we won't draw them in the following picture


$$D = \begin{array}{cccc|c} \circ & \circ & \cdot & \cdot & \cdot \\ \cdot & \cdot & \cdot & \cdot & \cdot \\ \cdot & \circ & \cdot & \circ & \circ \\ \hline \cdot & \circ & \cdot & \circ & \cdot \end{array}$$

Let  $D_1$  be the subdiagram on rows 1, 2, 3 and columns 1, 2, 3, 4 which corresponds to the pattern  $31524 = \text{fl}(31624)$ , so  $D_1 \simeq D(31524)$ .

A complete James-Peel tree  $\mathcal{T}_1$  for  $D_1$  is



where  $A_1 \simeq (3, 1)$ ,  $A_2 \simeq (2, 2)$ . The James-Peel tree  $\mathcal{T}_1$  for  $D_1$  induces the following James-Peel tree  $\mathcal{T}$  for  $D$



where  $B_{31} = R_{3 \rightarrow 1}D$  and  $B_{22} = C_{4 \rightarrow 1}D$  with

$$B_{31} = \begin{array}{cccc|c} \circ & \circ & \cdot & \circ & \circ \\ \cdot & \cdot & \cdot & \cdot & \cdot \\ \cdot & \circ & \cdot & \cdot & \cdot \\ \hline \cdot & \circ & \cdot & \circ & \cdot \end{array} \quad B_{22} = \begin{array}{cccc|c} \circ & \circ & \cdot & \cdot & \cdot \\ \cdot & \cdot & \cdot & \cdot & \cdot \\ \circ & \circ & \cdot & \cdot & \circ \\ \hline \circ & \circ & \cdot & \cdot & \cdot \end{array}$$

Following the proof of Lemma 3.18, we next apply leftward column moves to the lower left subdiagrams  $F'_1$  to get  $(F'_1)^{\min}$ , and upward row moves to the upper right subdiagrams  $(F'_2)$  to get  $(F'_2)^{\max}$ :

$$\tilde{B}_{31} = C_{4 \rightarrow 1} B_{31} = \begin{array}{cccc|c} \circ & \circ & \cdot & \circ & \circ \\ \cdot & \cdot & \cdot & \cdot & \cdot \\ \cdot & \circ & \cdot & \cdot & \cdot \\ \hline \circ & \circ & \cdot & \cdot & \cdot \end{array} \quad \tilde{B}_{22} = R_{3 \rightarrow 1} B_{22} = \begin{array}{cccc|c} \circ & \circ & \cdot & \cdot & \circ \\ \cdot & \cdot & \cdot & \cdot & \cdot \\ \circ & \circ & \cdot & \cdot & \cdot \\ \hline \circ & \circ & \cdot & \cdot & \cdot \end{array}$$

At this point we would apply James-Peel moves to the lower right subdiagram, but it is empty so there's nothing to do. Finally, we apply leftward column moves and rightward row moves to make all four subdiagrams into Ferrers diagrams (up to trailing empty rows and columns):

$$\tilde{C}_{31, \emptyset} = R_{3 \rightarrow 2} C_{4 \rightarrow 3} C_{2 \rightarrow 1} \tilde{B}_{31} = \begin{array}{cccc|c} \circ & \circ & \circ & \cdot & \circ \\ \circ & \cdot & \cdot & \cdot & \cdot \\ \cdot & \cdot & \cdot & \cdot & \cdot \\ \hline \circ & \circ & \cdot & \cdot & \cdot \end{array} \quad \tilde{C}_{22, \emptyset} = R_{3 \rightarrow 2} \tilde{B}_{22} = \begin{array}{cccc|c} \circ & \circ & \cdot & \cdot & \circ \\ \circ & \circ & \cdot & \cdot & \cdot \\ \cdot & \cdot & \cdot & \cdot & \cdot \\ \hline \circ & \circ & \cdot & \cdot & \cdot \end{array}$$

Now, taking unions before additions as the order of operations

$$\begin{aligned} (\tilde{C}_{31, \emptyset})^{\max} &= (3, 1) \cup (2) + (1) \cup \emptyset = (3, 2, 1) + (1) = (4, 2, 1), \\ (\tilde{C}_{22, \emptyset})^{\max} &= (2, 2) \cup (2) + (1) \cup \emptyset = (2, 2, 2) + (1) = (3, 2, 2). \end{aligned}$$

For the injection  $\iota : M(D_1) \hookrightarrow M(D)$  we therefore take  $\iota(3, 1) = (4, 2, 1)$  and  $\iota(2, 2) = (3, 2, 2)$ . Indeed,  $s_{D_1} = F_{31524} = s_{32/1} = s_{31} + s_{22}$ , while  $s_D = F_{316524} = s_{322} + s_{331} + s_{421}$ .

#### 4. TRANSITIONS AS JAMES-PEEL MOVES

Recall the following notation from Section 2. Given a permutation  $w$ , take  $r$  maximal with  $w(r) > w(r+1)$ , then  $s > r$  maximal with  $w(s) < w(r)$ . The set of transitions of  $w$  is

$$T(w) = \{wt_{rs}t_{rj} : \ell(wt_{rs}t_{rj}) = \ell(w)\}, \quad (9)$$


or else  $T(1 \times w)$  if the set on the right is empty. Note that  $wt_{rs}t_{rj} \in T(w)$  if and only if  $w(j) < w(s)$  and there is no  $j < j' < r$  with  $w(j) < w(j') < w(s)$ .

Upon taking diagrams of permutations, each transition corresponds to a sequence of James-Peel moves.

**Lemma 4.1.** *Given a permutation  $w$ , let  $r, s$  be as above and take  $w' = wt_{rs}t_{rj} \in T(w)$ . Then*

$$D(w') = R_{r \rightarrow j} C_{w(s) \rightarrow w(j)} D(w) = C_{w(s) \rightarrow w(j)} R_{r \rightarrow j} D(w).$$

*Proof.* We will show that the change in passing from  $D(w)$  to  $D(w')$  is as follows:



where we move the cells in each shaded region of  $D(w)$  into the corresponding (formerly cell-free) shaded region of  $D(w')$ , and also move the cell  $(r, w(s))$ , denoted by  $\circ$  above, to  $(j, w(j))$ . Here only the region  $[j, r] \times [w(j), w(s)]$  together with row  $s$  and column  $w(r)$  have been drawn. We will show the rest of the diagram remains

unchanged. We use  $\cdots$  and  $\vdots$  to denote a sequence of empty cells of arbitrary length.

Consider row-by-row the effect on diagrams of passing from  $w$  to  $w'$ . It is clear that rows  $k < j$  of  $D(w')$  match those of  $D(w)$ . Rows  $k > s$  also match: indeed, they are all empty.

In row  $j$ , by passing from  $D(w)$  to  $D(w')$  we could only gain cells. Specifically, a cell is gained in column  $w(k)$  if and only if the following equivalent conditions hold:

- $w(j) < w(k) < w(s)$  and  $k > j$ , or  $w(k) = w(j)$
- $w(j) < w(k) < w(s)$  and  $k > r$ , or  $w(k) = w(j)$
- $(r, w(k)) \in D(w)$  and  $w(j) < w(k)$ , or  $w(k) = w(j)$ .

On the other hand, in row  $r$ , we could only lose cells. A cell is lost in column  $w(k)$  if and only if following equivalent conditions hold:

- $w(j) < w(k) < w(r)$  and  $k > r$
- $w(j) < w(k) < w(s)$  and  $k > r$ , or  $w(k) = w(s)$
- $(r, w(k)) \in D(w)$  and  $w(j) < w(k)$ , or  $w(k) = w(s)$ .

Thus, the effect of passing from  $w$  to  $w'$  on rows  $j$  and  $r$  is to move all cells in row  $r$  between columns  $w(j)$  and  $w(s)$  up to row  $j$ , and to move  $(r, w(s))$  to  $(j, w(j))$ .

Now say  $j < k < r$ . The only column in which a cell could be gained in row  $k$  is column  $w(j)$ , which happens if and only if the following equivalent conditions hold:

- $w(k) > w(j)$
- $w(k) > w(s)$
- $(k, w(s)) \in D(w)$ .

Conversely, if there is a cell in row  $k$  and column  $w(s)$  of  $D(w)$ , it is lost in  $D(w')$ .

So at least within the region  $[j, r] \times [w(j), w(s)]$ , one does obtain  $D(w')$  from  $D(w)$  by performing the indicated James-Peel moves. To show that in fact  $D(w') = R_{r \rightarrow j} C_{w(s) \rightarrow w(j)} D(w)$ , we must show that these James-Peel moves do not move any cells outside of  $[j, r] \times [w(j), w(s)]$ . That is:

- If  $(k, w(s)) \in D(w)$  for  $k < j$  or  $k > r$ , then  $(k, w(j)) \in D(w)$ .
- If  $(r, w(k)) \in D(w)$  for  $w(k) < w(j)$  or  $w(k) > w(s)$ , then  $(j, w(k)) \in D(w)$ .

For (i), rows  $k > r$  are empty, so assume  $k < j$  and  $(k, w(s)) \in D(w)$ . Then  $w(k) > w(s) > w(j)$  and  $k < j$  give  $(k, w(j)) \in D(w)$ . For (ii),  $(r, w(s))$  is the rightmost cell in row  $r$  by the choice of  $r, s$ , so assume  $w(k) < w(j)$  and  $(r, w(k)) \in D(w)$ . Then  $(j, w(k)) \in D(w)$ , because  $j < r < k$  and  $w(k) < w(j)$ .  $\square$



**Theorem 4.2.** *For a permutation  $w$ , the diagram  $D(w)$  has a complete James-Peel tree.*

*Proof.* If  $w$  is vexillary, the tree with one vertex  $D(w)$  and no edges is a complete James-Peel tree for  $D(w)$ . Otherwise, let  $v^1, \dots, v^p$  be the transitions of  $w$ , say  $v^i = wt_{rst}t_{rj_i}$  where  $s > r > j_1 > \dots > j_p$ . Then  $w(j_1) < \dots < w(j_p) < w(s) < w(r)$ , so  $\text{fl}(w(j_p) \dots w(j_1)w(r)w(s)) = p \dots 1(p+2)(p+1)$ , and  $D(p \dots 1(p+2)(p+1))$  is exactly  $(p-1, \dots, 1) \cdot (1)$  after removing an empty row and column. Thus,  $D(w)$  contains  $(p-1, \dots, 1) \cdot 1$  as a subdiagram in rows  $j_p, \dots, j_2, r$  and columns  $w(j_1), \dots, w(j_{p-1}), w(s)$ .

Let

$$D_i = \begin{cases} R_{r \rightarrow j_i} C_{w(s) \rightarrow w(j_i)} D(w) & \text{if } 1 < i < p \\ C_{w(s) \rightarrow w(j_1)} D(w) & \text{if } i = 1 \\ R_{r \rightarrow j_p} D(w) & \text{if } i = p \end{cases}$$

The diagrams  $D_i$  are exactly those produced by Corollary 3.7, and  $\bigoplus_{i=1}^p S^{D_i} \hookrightarrow S^{D(w)}$ .

Let  $\mathcal{T}$  be the James-Peel tree with root  $D(w)$  and children  $D_i$ , where  $D(w)$  is connected to  $D_i$  by an edge labeled with the appropriate James-Peel move(s). Next, connect  $D_1$  to a child  $E_1 = R_{r \rightarrow j_1} D_1$  by an edge labeled  $R_{r \rightarrow j_1}$ , and  $D_p$  to a child  $E_p = C_{w(s) \rightarrow w(j_p)} D_p$  by an edge labeled  $C_{w(s) \rightarrow w(j_p)}$ . The leaves  $E_1, D_2, \dots, D_{p-1}, E_p$  of  $\mathcal{T}$  are now exactly  $D(v^1), \dots, D(v^p)$  by Lemma 4.1. Attach to each  $D(v^i)$  the tree inductively produced for  $v^i$  by transitions and so on until every leaf is the diagram of a vexillary permutation.

The tree  $\mathcal{T}$  is still a James-Peel tree for  $D(w)$ . By construction, its leaves are the diagrams of the leaves of the Lascoux-Schützenberger tree of  $w$ . The equation  $s_{D(w)} = \sum_v s_{\text{shape}(v)}$  from Section 2, with  $v$  running over the leaves of the L-S tree, implies that  $\mathcal{T}$  is complete.  $\square$

Let  $JP(w)$  be the James-Peel tree for  $D(w)$  constructed in Theorem 4.2. Corollary 3.19 and Theorem 4.2 now yield our first main result.

**Theorem 1.1.** Let  $v, w$  be permutations with  $w$  containing  $v$  as a pattern. There is an injection  $\iota : \mathcal{EG}(v) \hookrightarrow \mathcal{EG}(w)$  such that if  $P \in \mathcal{EG}(v)$ , then  $\text{shape}(P) \subseteq \text{shape}(\iota(P))$ . Moreover, if  $P, P'$  have the same shape, so do  $\iota(P), \iota(P')$ .

**Corollary 4.3.** *If a permutation  $w$  is  $k$ -vexillary and  $v$  is a pattern in  $w$ , then  $v$  is  $k$ -vexillary.*

**Corollary 4.4.** *If  $v$  is a pattern in  $w$  and  $F_w$  is multiplicity-free, so is  $F_v$ . More generally, if  $\langle F_w, s_\lambda \rangle \leq k$  for all  $\lambda$  then  $\langle F_v, s_\mu \rangle \leq k$  for all  $\mu$ .*

**Remark 4.5.** Theorem 1.1 shows the existence of an injection  $\mathcal{EG}(v) \hookrightarrow \mathcal{EG}(w)$  which respects inclusion of shapes for  $v$  a pattern contained in  $w$ , but an explicit map on tableaux is lacking. The Edelman-Greene correspondence shows that this is equivalent to an injection  $\text{Red}(v) \hookrightarrow \text{Red}(w)$  which is an inclusion on the shapes of Edelman-Greene insertion tableaux. Tenner's [32] characterization of vexillary permutations yields an explicit injection in the case where  $v$  is vexillary.

**Remark 4.6.** We note that Crites, Panova and Warrington have studied the connection between the shape of a permutation under the RSK correspondence and pattern containment [5]. The injection given in Theorem 1.1 on shapes is quite

different since the Edelman-Greene tableaux of a permutation are based on the reduced words instead of the one-line notation. At this time, we don't know of a connection between their work and our injection.

So far we have only used Corollary 3.19, but the full strength of Lemma 3.18 yields another interesting result.

**Theorem 4.7.** *Let  $w \in S_n$  be a permutation and  $I \subseteq [n]$ . If  $u_1$  is the subsequence of  $w$  in positions  $I$ , and  $u_2$  the subsequence in positions  $[n] \setminus I$ , then*

$$EG(w) \geq EG(\text{fl}(u_1)) \cdot EG(\text{fl}(u_2)).$$

## 5. $k$ -VEXILLARY PERMUTATIONS

In this section we show that the property of  $k$ -vexillarity is characterized by avoiding a finite set of patterns for any  $k$ . The key step is to remove some inessential moves from the James-Peel tree for  $D(w)$ , namely those which only permute rows or columns.

If  $D$  is an arbitrary diagram, and  $\sigma, \tau$  are permutations, let  $(\sigma, \tau)D$  be the diagram  $\{(\sigma(i), \tau(j)) : (i, j) \in D\}$ . Given a James-Peel tree  $\mathcal{T}$  for  $D$ , let  $(\sigma, \tau)\mathcal{T}$  denote the James-Peel tree for  $(\sigma, \tau)D$  gotten by replacing every James-Peel move  $R_{x \rightarrow y}$  labeling an edge of  $\mathcal{T}$  by  $R_{\sigma(x) \rightarrow \sigma(y)}$ , and every move  $C_{x \rightarrow y}$  by  $C_{\tau(x) \rightarrow \tau(y)}$ , and relabeling vertices accordingly. Whenever a move labeling an edge  $e$  of a James-Peel tree just permutes rows or columns, we can eliminate that move from the tree at the cost of relabeling rows and columns of James-Peel moves below  $e$ , as follows.

**Definition 5.1.** Given a James-Peel tree  $\mathcal{T}$  of a diagram  $D$ , define the *reduced James-Peel tree*  $\text{red}(\mathcal{T})$  of  $D$  inductively.

- If  $D$  has no children in  $\mathcal{T}$ , then  $\text{red}(\mathcal{T}) = \mathcal{T}$ .
- If  $D$  has just one child  $F$ , and  $D = (\sigma, \tau)F$  for some  $\sigma, \tau \in S_\infty$ , let  $\mathcal{T}_1$  be the subtree of  $\mathcal{T}$  below  $F$  with root  $F$ . Then  $\text{red}(\mathcal{T}) = (\sigma, \tau)\text{red}(\mathcal{T}_1)$ .
- If  $D$  has at least two children  $F_1, F_2, \dots, F_p$  or  $D$  has one child  $F_1$  not equivalent to  $D$ , let  $\mathcal{T}_i$  be the subtree of  $\mathcal{T}$  below  $F_i$  with root  $F_i$ . Then  $\text{red}(\mathcal{T})$  is  $\mathcal{T}$  with each  $\mathcal{T}_i$  replaced by  $\text{red}(\mathcal{T}_i)$ .

**Definition 5.2.** A rooted tree is *bushy* if every non-leaf vertex has at least two children.

**Lemma 5.3.** *If  $\mathcal{T}$  is a complete James-Peel tree for  $D$ , then  $\text{red}(\mathcal{T})$  is a complete James-Peel tree for  $D$ . Furthermore,  $\text{red}(\mathcal{T})$  is bushy.*

*Proof.* Note that  $\text{red}(\mathcal{T})$  is still a James-Peel tree for  $D$ . As equivalent diagrams have isomorphic Specht modules, if  $\mathcal{T}$  is complete then so is  $\text{red}(\mathcal{T})$ .

Next, for any vertex  $A$  of  $\mathcal{T}$ , the subtree of  $\mathcal{T}$  below  $A$  is itself a complete James-Peel tree for  $A$ . In particular,  $S^A$  is determined by the leaves below it. Therefore, if  $A$  has only a single child  $B$  in  $\mathcal{T}$ , then  $S^A$  and  $S^B$  are isomorphic.


Now suppose  $\mathcal{T}$  is not bushy. The only way this can happen is if  $\mathcal{T}$  has a vertex  $A$  with only one child  $B$ , but  $A$  and  $B$  are not equivalent. There is a James-Peel move relating  $A, B$  (or a sequence of them, but we can consider them one at a time), say  $B = R_{a \rightarrow b}A$ . If one of rows  $a$  and  $b$  of  $A$  is contained in the other, then  $R_{a \rightarrow b}A$  is simply  $A$  with those two rows interchanged, so rows  $a$  and  $b$  are not comparable under inclusion since  $A$  and  $B$  are not equivalent. There are cells  $(a, j_1), (b, j_2) \in A$

with  $(a, j_2), (b, j_1) \notin A$ . By Theorem 3.1,  $S^B \oplus S^{C_{j_1 \rightarrow j_2} A} \hookrightarrow S^A$ . As  $S^{C_{j_1 \rightarrow j_2} A} \neq 0$ ,  $S^B$  is not isomorphic to  $S^A$ . This contradicts the previous paragraph, so  $\mathcal{T}$  must be bushy.  $\square$

**Lemma 5.4.** *The number of edges in a bushy tree with  $k$  leaves is at most  $2k - 2$ .*

*Proof.* This follows by induction on the number of leaves.  $\square$

Recall  $JP(w)$  is the James-Peel tree for  $D(w)$  constructed in Theorem 4.2, and let  $RJP(w) = \text{red}(JP(w))$ . In the vicinity of a vertex  $D(v)$ ,  $JP(w)$  looks like this:



Here the  $v^i = vt_{rs}t_{rj_i}$  are the transitions of  $v$ , with  $j_1 > \dots > j_p$ . The rows of  $D(v)$  involved in row moves are  $r, j_1, \dots, j_p$ , and the columns involved in column moves are  $v(s), v(j_1), \dots, v(j_p)$ . In the figure above, we have elongated two of the paths for the proofs to come.

**Lemma 5.5.** *Suppose  $v$  has transitions  $v^1, \dots, v^p$  as above. Then  $D(v^1)$  is equivalent to  $C_{v(s) \rightarrow v(j_1)} D(v)$ , and  $D(v^p)$  is equivalent to  $R_{r \rightarrow j_p} D(v)$ .*

*Proof.* By Lemma 4.1,


$$D(v^1) = C_{v(s) \rightarrow v(j_1)} R_{r \rightarrow j_1} D(v)$$

and

$$D(v^p) = R_{r \rightarrow j_p} C_{v(s) \rightarrow v(j_p)} D(v).$$

It suffices to check that column  $v(s)$  of  $D(v)$  contains column  $v(j_p)$ , and that row  $r$  contains row  $j_1$ . Suppose the first of these fails, that there is  $(i, v(j_p)) \in D(v)$  with  $(i, v(s)) \notin D(v)$ . Choose the maximal such  $i$ . Then  $vt_{rs}t_{ri}$  is a transition of  $v$ , which is impossible since  $i < j_p$ . The argument for the row containment is analogous.  $\square$

Thus, upon passing to  $RJP(w)$ , the edges  $A-D(v^1)$  and  $B-D(v^p)$  are contracted. For a diagram  $D$ , write  $[D]$  for the equivalence class of diagrams containing  $D$ . We use this notation below when we have a diagram equivalent to  $D$  but don't need to specify exactly what the diagram is. In the vicinity of a vertex  $[D(v)]$ ,  $RJP(w)$  has the form



Strictly speaking, we haven't shown that both moves on the edges labeled  $RC$  survive in  $RJP(w)$ , but this won't be important. We therefore will speak of  $R$ -edges,  $C$ -edges, and  $RC$ -edges of  $RJP(w)$ , each non-leaf vertex having exactly one  $R$ -edge and one  $C$ -edge leading to children.

Now suppose  $\mathcal{T}$  is a subtree of  $RJP(w)$  with the same root. Let  $R(\mathcal{T})$  be the union of  $\{a, b\}$  over all  $R_{a \rightarrow b}$  appearing in  $\mathcal{T}$ , and  $C(\mathcal{T})$  the union of  $\{c, d\}$  over all  $C_{c \rightarrow d}$  appearing in  $\mathcal{T}$ . Write  $R(\mathcal{T}) \cup w^{-1}C(\mathcal{T}) = \{i_1 < \cdots < i_r\}$ , and define the permutation associated to this tree

$$w_{\mathcal{T}} = fl(w(i_1) \cdots w(i_r)).$$

**Remark 5.6.** In Section 2 we noted that, for convenience,  $w$  could be replaced by  $1^m \times w$  to remove the necessity of sometimes replacing  $v$  by  $1 \times v$  in the Lascoux-Schützenberger tree. The definition of  $w_{\mathcal{T}}$  above is then an abuse of notation, since we are really taking a subsequence of  $1^m \times w$ . However, rows and columns  $1, \dots, m$  of  $D(w)$  are empty, so are not affected at all by the James-Peel moves in  $RJP(w)$  or  $\mathcal{T}$ . This means that the subsequence defining  $w_{\mathcal{T}}$  occurs entirely after the  $m$ th position of  $1^m \times w$ , so we are free to shift it down by  $m$  and consider it as a subsequence of  $w$ . This applies also to Theorems 5.9 and 5.10 below.

We would like to bound the number of letters of  $w_{\mathcal{T}}$  in terms of the number of leaves of  $\mathcal{T}$ . Such a bound depends on the sizes of  $R(\mathcal{T})$  and  $C(\mathcal{T})$ , so the following definition is convenient to get good bounds.

**Definition 5.7.** A subtree  $\mathcal{T}$  of  $RJP(w)$  with root  $D(w)$  is *colorful* if each non-leaf vertex of  $\mathcal{T}$  has at least the two children corresponding to its  $R$ -edge and its  $C$ -edge. Thus, colorful implies bushy.

**Lemma 5.8.** *Say  $\mathcal{T}$  is a subtree of  $RJP(w)$  rooted at  $D(w)$  with  $k$  leaves. Then  $k \leq EG(w_{\mathcal{T}}) \leq EG(w)$ . If  $\mathcal{T}$  is colorful, then  $w_{\mathcal{T}} \in S_m$  for some  $m \leq 4k - 4$ .*

*Proof.* Up to relabeling rows and columns to account for flattening, the tree  $\mathcal{T}$  is a James-Peel tree for  $D(w_{\mathcal{T}})$  (not necessarily complete), so  $k \leq EG(w_{\mathcal{T}})$ . Theorem 1.1 implies  $EG(w_{\mathcal{T}}) \leq EG(w)$ .

Suppose  $\mathcal{T}$  is colorful. The number of letters in  $w_{\mathcal{T}}$  is at most  $|R(\mathcal{T})| + |C(\mathcal{T})|$ . Consider the vertex indexed by  $D(v)$  in the full tree  $JP(w)$ . Say  $v^i = vt_{rs}t_{rj_i}$  are the transitions of  $v$ , with  $j_1 > \cdots > j_p$ . The rows of  $D(v)$  involved in row moves are  $r, j_1, \dots, j_p$ , and the columns involved in column moves are  $v(s), v(j_1), \dots, v(j_p)$ . However,  $R_{r \rightarrow j_1}D(v) \simeq D(v)$  and  $C_{v(s) \rightarrow v(j_p)}D(v) \simeq D(v)$  by Lemma 5.5, so these edges are contracted in the reduced tree, so row  $j_1$  and column  $v(j_p)$  will not contribute to  $R(\mathcal{T})$  and  $C(\mathcal{T})$  respectively. Thus, if a vertex  $F$  (which is equivalent to some  $D(v)$ ) of  $\mathcal{T}$  has  $p$  children, the edges leading down from  $F$  contribute at

most  $p$  elements to each of  $R(\mathcal{T})$  and  $C(\mathcal{T})$ . Summing over all vertices,

$$\begin{aligned}
|R(\mathcal{T})| + |C(\mathcal{T})| &\leq 2 \deg(D(w)) + \sum_{\substack{F \in \mathcal{T} \\ F \neq D(w)}} 2(\deg(F) - 1) \\
&= 2 \left[ \sum_{F \in \mathcal{T}} \deg(F) \right] - 2|V(\mathcal{T})| + 2 \\
&= 4|E(\mathcal{T})| - 2(|V(\mathcal{T})| - 1) \\
&= 2|E(\mathcal{T})| \\
&\leq 4k - 4,
\end{aligned}$$

with the last inequality by Lemma 5.4.  $\square$

In particular, taking  $\mathcal{T} = RJP(w)$  in Lemma 5.8 gives the following theorem.

**Theorem 5.9.** *Any permutation  $w$  contains a pattern  $v \in S_m$  such that  $EG(w) = EG(v)$ , for some  $m \leq 4 EG(w) - 4$ .*

More generally, Lemma 5.8 lets us show that  $k$ -vexillarity is characterized by avoiding a *finite* set of patterns.

**Theorem 5.10.** *Say  $w$  is a permutation with  $EG(w) > k$ . Then  $w$  contains a pattern  $v \in S_m$  such that  $EG(v) > k$ , for some  $m \leq 4k$ .*

*Proof.* By Lemma 5.8, it suffices to exhibit a colorful subtree of  $RJP(w)$  rooted at  $D(w)$  with  $k + 1$  leaves. Construct such a tree  $\mathcal{T}$  as follows. First take  $\mathcal{T}$  to have only the vertex  $D(w)$ . Add the two children of  $D(w)$  corresponding to the  $R$ -edge and the  $C$ -edge. Continue adding the remaining children of  $D(w)$  until  $\mathcal{T}$  has  $k + 1$  leaves or all children have been added. If all children of  $D(w)$  have been added and  $\mathcal{T}$  has fewer than  $k + 1$  leaves, then since  $RJP(w)$  has at least  $k + 1$  leaves, there is a leaf  $F$  of  $\mathcal{T}$  with at least two children. Now repeat this process starting with  $F$  in place of  $D(w)$ . Iterating, eventually  $\mathcal{T}$  will have  $k + 1$  leaves, and is colorful by construction.  $\square$

**Corollary 5.11.** *A permutation  $w$  is  $k$ -vexillary if and only if it avoids all non- $k$ -vexillary patterns in  $S_m$  for  $1 \leq m \leq 4k$ .*

For  $k = 2$ , we can explicitly find all non-2-vexillary patterns in  $S_m$  for  $1 \leq m \leq 8$  and eliminate those containing a smaller non-2-vexillary pattern to find a minimal list.

**Theorem 5.12.** *A permutation  $w$  is 2-vexillary if and only if it avoids all of the following 35 patterns.*

21543	231564	315264	5271436	26487153	54726183	64821537
32154	241365	426153	5276143	26581437	54762183	64872153
214365	241635	2547163	5472163	26587143	61832547	65821437
214635	312645	4265173	25476183	51736284	61837254	65827143
215364	314265	5173264	26481537	51763284	61873254	65872143

This process is also feasible for  $k = 3$ , in which case we need to look at non-3-vexillary patterns up through  $S_{12}$ . Here we find that the bound in Corollary 5.11 is not sharp.

**Theorem 5.13.** *A permutation  $w$  is 3-vexillary if and only if it avoids a list of 91 patterns in  $S_6 \cup S_7 \cup S_8$ . For the full list of patterns, see*

<http://www.math.washington.edu/~billey/papers/k.vex.html>.

The 3-vexillary permutations have some interesting properties. First, in Section 7 we will show their Stanley symmetric functions are always multiplicity free. Second, their essential sets are relatively simple.

In [10], Fulton defined the *essential set* of a permutation  $w$ ,  $Ess(w)$ , to be the set of southeast corners of the connected components of the diagram  $D(w)$ . He showed that the rank conditions for the Schubert variety indexed by  $w$  need only be checked at cells in the essential set. Furthermore, he showed that the essential set of a vexillary permutation has no two cells  $(i_1, j_1)$  and  $(i_2, j_2)$  with  $i_1 < i_2$  and  $j_1 < j_2$ . Thus, the essential set lies along a lattice path going from the southwest corner of the diagram to the northeast using only north and east steps. See [27, Prop.4.6] for an alternative description of the essential set using minimal bigrassmannian elements not below  $w$  in Bruhat order.

One can characterize permutations whose essential set consists of two nonintersecting such lattice paths in terms of pattern avoidance.

**Lemma 5.14.** *A permutation  $w$  has essential set with no three cells  $(i_1, j_1)$ ,  $(i_2, j_2)$ , and  $(i_3, j_3)$  with  $i_1 < i_2 < i_3$  and  $j_1 < j_2 < j_3$  if and only if  $w$  avoids the 25 patterns*

214365	3251746	35172864	35281746	53182764
2416375	3251764	35182746	35281764	53271846
2417365	4216375	35182764	53172846	53271864
3152746	4216735	35271846	53172864	53281746
3152764	35172846	35271864	53182746	53281764

**Corollary 5.15.** *If a permutation  $w$  is 3-vexillary, its essential set does not contain any three cells  $(i_1, j_1)$ ,  $(i_2, j_2)$ ,  $(i_3, j_3)$  with  $i_1 < i_2 < i_3$  and  $j_1 < j_2 < j_3$ .*

*Proof.* None of the patterns in Lemma 5.14 are 3-vexillary, so this follows from Corollary 4.3.  $\square$

**Remark 5.16.** The essential set can be used to give a short proof that the Lascoux-Schützenberger tree is finite. First, the L-S tree can contain only finitely many  $w$  with more than one maximal transition, e.g. because  $F_w = \sum_v F_v$  for  $v$  running over transitions of  $w$ , and the coefficient of  $x_1 \cdots x_\ell$  in  $F_w$  is always positive. Second, if  $Ess(w)$  lies in a single row, then  $w$  is vexillary by Fulton's result above. Otherwise, if  $w$  is not vexillary but has exactly one maximal transition  $v = wt_{rs}t_{rj}$  where  $r$  is the largest index of a non-empty row in  $Ess(w)$ , then one can show by considering the diagram of the permutation that  $Ess(v) = Ess(w) \setminus \{(r, s)\} \cup \{(r-1, s-1)\}$ . The same argument holds if  $w$  must be replaced by  $1 \times w$  in the algorithm. Thus, either the distance between the top and bottom (non-empty) rows of the essential set strictly decreases upon passing from  $w$  to  $v$ , or this distance remains the same but the number of elements in the essential set in the bottom row decreases.

Searching through all non-4-vexillary permutations in  $S_{16}$  is currently beyond our computational capabilities. However, one does find that every non-4-vexillary permutation in  $S_{13}$  contains a proper non-4-vexillary pattern.

**Conjecture 1.** *A permutation  $w$  is 4-vexillary if and only if it avoids a list of 2346 patterns in  $S_6 \cup S_7 \cup \cdots \cup S_{12}$ .*

For the minimal list of non-4-vexillary patterns in  $S_{13}$ , see

<http://www.math.washington.edu/~billey/papers/k.vex.html>.

If one wants to compute or bound  $EG(w)$ , the Lascoux-Schützenberger tree is almost certainly more efficient than using our pattern characterizations. However, pattern characterizations lend themselves nicely to comparison, as exemplified in the proof of Corollary 5.15. The connection to patterns also leads to enumerative results relating to  $EG(w)$ , since there has been much work done on enumerating permutations avoiding a given set of patterns, for example [4].

## 6. DIAGRAM VARIETIES

Let  $\text{Gr}(k, n)$  denote the Grassmannian variety of  $k$ -planes in  $\mathbb{C}^n$ . For a diagram  $D$  contained in a  $k \times (n - k)$  rectangle, let  $\Omega_D^\circ$  be the set of  $k$ -planes given as row spans of the matrices

$$\{(I_k | A) : A \in M_{k \times (n-k)}, A_{ij} = 0 \text{ if } (i, j) \in D\}.$$

Here  $I_k$  is the  $k \times k$  identity matrix. Let  $\Omega_D$  be the closure of  $\Omega_D^\circ$  in  $\text{Gr}(k, n)$ . We call  $\Omega_D$  the *diagram variety* associated to  $D$  (though it also depends on  $k$  and  $n$ ).

Recall that partitions contained in the rectangle  $k \times (n - k)$  are in bijection with  $k$ -subsets of  $[n]$ . Specifically,  $\lambda$  corresponds to the set

$$B_\lambda = \{n - k + i - \lambda_i : 1 \leq i \leq k\}.$$

Write

$$B_\lambda = \{b_1 < \cdots < b_k\} \quad \text{and} \quad [n] \setminus B_\lambda = \{c_1 < \cdots < c_{n-k}\},$$

and define a permutation  $w_\lambda$  of  $[n]$  in one-line notation by  $w_\lambda = b_1 \cdots b_k c_1 \cdots c_{n-k}$ .

Taking the standard basis  $e_1, \dots, e_n$  of  $\mathbb{C}^n$ , define a complete flag  $F_\bullet$  by

$$F_i = \langle e_1, \dots, e_i \rangle.$$

The *Schubert cell* is defined as

$$X_\lambda^\circ = \{X \in \text{Gr}(k, n) : \dim(X \cap F_i) > \dim(X \cap F_{i-1}) \text{ if and only if } i \in B_\lambda\},$$


and its closure in the Zariski topology on  $\text{Gr}(k, n)$  is the *Schubert variety*  $X_\lambda$  [11]. The codimension of  $X_\lambda$  is  $|\lambda|$  as defined. In particular, the diagram variety  $\Omega_\lambda$  indexed by the Ferrers diagram for  $\lambda$  can be written as  $\Omega_\lambda = X_\lambda w_\lambda$  since right multiplication by a permutation matrix permutes columns of the matrices in  $X_\lambda$ . Thus diagram varieties generalize the Schubert varieties up to change of basis.

Let  $\sigma_\lambda$  be the cohomology class in  $H^{2|\lambda|}(\text{Gr}(k, n), \mathbb{Z})$  associated to  $\Omega_\lambda$ . One has the following classical facts about the *Schubert classes*  $\sigma_\lambda$  (see [11]).

- The classes  $\sigma_\lambda$  for  $\lambda$  varying over all partitions contained in  $(k^{n-k})$  form a  $\mathbb{Z}$ -basis of  $H^*(\text{Gr}(k, n), \mathbb{Z})$ .
- Let  $\Lambda$  denote the ring of symmetric functions over  $\mathbb{Z}$  in infinitely many variables. Then  $\sigma_\lambda \mapsto s_\lambda$  defines an isomorphism of rings

$$\phi : H^*(\text{Gr}(k, n), \mathbb{Z}) \xrightarrow{\sim} \Lambda / \langle s_\lambda : \lambda \not\subseteq (k^{n-k}) \rangle.$$

The second fact suggests a relationship to Specht modules. For example, consider the skew shape  $\lambda \cdot \mu$  obtained by placing  $\lambda$ ,  $\mu$  together with no cell from  $\lambda$  in the same row or column as a cell from  $\mu$ :



Suppose  $\lambda \cdot \mu$  is contained in  $(k^{n-k})$ . The multiplicity of the irreducible  $S^\nu$  in  $S^{\lambda \cdot \mu}$  is the Littlewood-Richardson coefficient  $c_{\lambda\mu}^\nu$ . This is also the coefficient of  $s_\nu$  in the Schur expansion of  $s_{\lambda \cdot \mu} = s_\lambda s_\mu$ , hence the coefficient of  $\sigma_\nu$  in  $\sigma_{\lambda \cdot \mu}$  [10].

Every closed subvariety of the Grassmannian has an associated cohomology class [9]. In particular, each diagram variety  $\Omega_D$  has an associated class  $\sigma_D$  which can be expressed as a symmetric function via  $\phi$ . Liu studied diagram varieties and their cohomology classes in [20], and made the following conjecture, which generalizes the remarks above.

**Conjecture 2** (Liu's conjecture). *Let  $D \subseteq (k^{n-k})$ . If the generalized Schur function  $s_D$  associated to  $D$  expands into classical Schur functions as*

$$s_D = \sum_{\lambda} c_{\lambda}^D s_{\lambda},$$

*then the cohomology class for  $\Omega_D$  has the same expansion coefficients*

$$\sigma_D = \sum_{\lambda} c_{\lambda}^D \sigma_{\lambda}.$$

*Thus, the map  $\phi$  sends  $\sigma_D$  to  $s_D$ .*

**Remark 6.1.** One can show that if  $D$  is contained in  $(k^{n-k})$ , so is any  $\lambda$  with  $S^{\lambda} \hookrightarrow S^D$  (this is obvious when  $D$  has a complete James-Peel tree).

Let  $D^\vee$  denote the complement of  $D$  in the rectangle  $(k^{n-k})$ . Conjecture 2 is known in several special cases.

**Theorem 6.2** ([20, Proposition 5.5.3]). *Conjecture 2 holds when  $D^\vee$  is a skew shape  $\lambda/\mu$ .*

Given a diagram  $D$  in  $[k] \times [n-k]$ , Liu constructs a bipartite graph  $G_D = ([k], E, [n-k])$  where  $E$  contains an edge  $(i, j)$  if and only if  $(i, j) \in D$ .

**Theorem 6.3** ([20, Theorem 5.4.3]). *Conjecture 2 holds for a diagram  $D$  provided  $G_{D^\vee}$  is a forest.*

A key tool in Liu's proof of Theorem 6.3 is an analogue of Theorem 3.1, albeit with stronger hypotheses. Given  $\alpha_1, \alpha_2 \in H^*(\text{Gr}(k, n))$ , write  $\alpha_1 \geq \alpha_2$  if  $\alpha_1 - \alpha_2$  is a nonnegative linear combination of the Schubert classes  $\sigma_\lambda$ .

**Proposition 6.4** ([20, Proposition 5.3.4]). *Let  $D$  be a diagram, and  $(i_1, j_1), (i_2, j_2) \in D$  such that  $(i_1, j_2), (i_2, j_1) \notin D$ . Suppose also that if  $(p, j_1), (p, j_2) \in D$ , then row  $p$  of  $D$  contains rows  $i_1$  and  $i_2$ . Then*

$$\sigma_{D^\vee} \geq \sigma_{(R_{i_1 \rightarrow i_2} D)^\vee} + \sigma_{(C_{j_1 \rightarrow j_2} D)^\vee}.$$

Like the Schur function  $s_D$ ,  $\sigma_D$  only depends on  $D$  up to equivalence.

**Lemma 6.5.** *If  $D, D'$  are equivalent diagrams, then  $\sigma_D = \sigma_{D'}$ .*



*Proof.* Permuting columns of  $D$  corresponds to a change of basis of  $\mathbb{C}^n$ , which does not change  $\sigma_D$  since multiplication by an element of  $\mathrm{GL}_n$  induces a rational equivalence on varieties in  $\mathrm{Gr}(k, n)$  [9]. As for rows, identify a permutation  $v$  with a permutation matrix. If  $(I|A)$  is a matrix representing a point of  $\Omega_D$ , then  $(I|vA)$  represents the same  $k$ -plane as  $(v^{-1}I|A)$ , and so by permuting the first  $k$  basis vectors according to  $v$ , we see that  $\sigma_D$  is not affected by permuting rows of  $D$ .  $\square$

Liu proves a weaker result than Conjecture 2 in the case of diagram varieties for the complement of a permutation diagram.


**Proposition 6.6** ([20, Proposition 5.5.4]). Under the Plücker embedding  $\Omega_{D(w)^\vee} \hookrightarrow \mathrm{Gr}(k, n) \hookrightarrow \mathbb{P}^{\binom{n}{k}-1}$ , the degree of  $\Omega_{D(w)^\vee}$  is  $\dim S^{D(w)} = |\mathrm{Red}(w)|$ .

**Remark 6.7.** Note that this is what the degree must be if Conjecture 2 is to hold. This is because  $\sigma_{(1)}$  is the class of a hyperplane intersected with  $\mathrm{Gr}(k, n)$  in the Plücker embedding, so the degree of  $\Omega_{D^\vee}$  is the coefficient of  $\sigma_{(k^{n-k})}$  in  $\sigma_{D^\vee} \cdot \sigma_{(1)}^{|D|}$  [9]. When  $D = \lambda$  is a partition, it is easy to see using Pieri's rule that this coefficient is the number of standard Young tableaux of shape  $\lambda$ , which is the dimension of  $S^\lambda$ . The claim for general  $D$  follows by linearity.


Thanks to Proposition 6.6, in order to prove Conjecture 2 for  $\Omega_{D(w)^\vee}$ , it is enough to show that  $\phi(\sigma_{D(w)^\vee}) \geq s_{D(w)^\vee}$ . This follows immediately from Theorem 4.2 and Proposition 6.4 whenever the conditions of Proposition 6.4 are satisfied throughout  $JP(w)$ , the James-Peel tree for  $D(w)$ .

**Theorem 6.8.** Conjecture 2 holds for  $D(w)^\vee$  whenever each James-Peel move in  $JP(w)$  satisfies the conditions of Proposition 6.4, or else is an equivalence of diagrams.

We can give some conditions on  $w$  which guarantee that Conjecture 2 holds for  $D(w)^\vee$ . First, suppose  $D$  is any diagram such that there are  $i_1 < i_2$ ,  $j_1 < j_2$ , and  $p$  such that  $(i_1, j_1), (i_2, j_2), (p, j_1), (p, j_2) \in D$  but  $(i_1, j_2), (i_2, j_1) \notin D$ . Suppose also that row  $p$  of  $D$  does not contain one of rows  $i_1, i_2$ , so that there is  $j$  such that  $(p, j) \notin D$  but  $(i_k, j) \in D$  for one of  $k = 1, 2$ . We draw the possible subdiagrams of  $D$  in rows  $i_1, i_2, p$  and columns  $j_1, j_2, j$ , using  $\bullet$  for the cells  $(i_1, j_1), (j_1, j_2)$  and  $\circ$  for the cells  $(p, j_1), (p, j_2), (i_k, j)$ , with  $*$  for a cell which may or may not be in  $D$ :



Now suppose  $D$  is *northwest*: that if  $i_1 < i_2$ ,  $j_1 < j_2$  and  $(i_1, j_2), (i_2, j_1) \in D$ , then  $(i_1, j_1) \in D$ . This rules out all the subdiagrams above except



Each of these three (sub)diagrams has Schur function  $s_{221} + s_{311} + s_{32}$ . Moreover, each one has a complete James-Peel tree (e.g. because they are equivalent to permutation diagrams), so Corollary 3.19 implies that  $s_D$  has at least 3 Schur function terms. More generally, if  $D$  labels a vertex of a James-Peel tree for some other diagram  $E$ , then  $s_E$  has at least 3 Schur function terms. Therefore, if  $s_E$  has at most 2 Schur function terms and  $E$  has a complete James-Peel tree, then Conjecture 2 holds for  $E$ . In particular, permutation diagrams are always northwest.

**Theorem 6.9.** *If  $w \in S_n$  is 2-*vexillary*, then Conjecture 2 holds for  $D(w)^\vee$ .*

One can get somewhat better results by various tricks. For example, the homeomorphism  $\text{Gr}(k, n) \rightarrow \text{Gr}(n - k, n)$  given by orthogonal complement sends  $\Omega_D$  to  $\Omega_{D^t}$  after a change of basis, so the induced isomorphism  $H^*(\text{Gr}(n - k, n)) \rightarrow H^*(\text{Gr}(k, n))$  sends  $\sigma_{D^t}$  to  $\sigma_D$ . Therefore, the coefficient of  $\sigma_\lambda$  in  $\sigma_D$  is the same as the coefficient of  $\sigma_{\lambda^t}$  in  $\sigma_{D^t}$ . Since the analogous statement is true for Schur functions of diagrams, Conjecture 2 holds for  $D$  if and only if it does for  $D^t$ .

On the other hand, the condition of Proposition 6.4 is not symmetric under transpose. That is, if  $D$  contains one of the three bad subdiagrams above, we may try transposing it, applying the appropriate James-Peel move with Proposition 6.4, and transposing back. As above, one can write down the subdiagrams which prevent this from going through, and find that their Schur functions all have at least 4 terms. This gives

**Theorem 6.10.** *If  $w \in S_n$  is 3-*vexillary*, then Conjecture 2 holds for  $D(w)^\vee$ .*

Theorems 6.2 and 6.3 prove Conjecture 2 when  $D(w)$  is equivalent to a skew shape or a forest, and we note that these have nice statements in terms of pattern-avoidance as well. It is shown in [2] that if  $w$  is 321-avoiding, then  $D(w)$  is equivalent to a skew shape. As for forests,

**Theorem 6.11.** *The graph  $G_{D(w)}$  is a forest if and only if  $w$  avoids 3412, 4312, 3421, and 4321.*

The permutations avoiding these four patterns have been studied by Elizalde [7] in the context of almost increasing permutations.

*Proof.* Clearly, if  $D(w)$  has the property that the graph  $G_{D(w)}$  is a forest, then so do all its subdiagrams. Therefore,  $w$  cannot contain 3412, 4312, 3421, or 4321, as one easily checks that none of these have graphs which are forests.

For the converse, suppose that  $G = G_{D(w)}$  is not a forest. Take a sequence of distinct cells  $b_1, \dots, b_m \in D$  forming a cycle in  $G$ . Choose  $i$  so that  $b_i = (p, q)$  with  $q$  maximal, then with  $p$  maximal for that  $q$ . The three cells  $b_{i-1}, b_i, b_{i+1}$  then form the pattern  $\begin{smallmatrix} \circ & & \circ \\ \circ & & \circ \end{smallmatrix}$  in  $D(w)$ . Since  $D(w)$  is northwest, it therefore contains



as a subdiagram. After adding  $\times$  to these rows and columns as usual for a permutation diagram, we must end up with one of the four following subdiagrams:

$$\begin{array}{cccc}
 \circ & \circ & \times & \cdot \\
 \circ & \circ & \cdot & \times \\
 \times & \cdot & \cdot & \cdot \\
 \cdot & \times & \cdot & \cdot
 \end{array}
 \quad
 \begin{array}{cccc}
 \circ & \circ & \circ & \times \\
 \circ & \circ & \times & \cdot \\
 \times & \cdot & \cdot & \cdot \\
 \cdot & \times & \cdot & \cdot
 \end{array}
 \quad
 \begin{array}{cccc}
 \circ & \circ & \times & \cdot \\
 \circ & \circ & \cdot & \times \\
 \circ & \times & \cdot & \cdot \\
 \times & \cdot & \cdot & \cdot
 \end{array}
 \quad
 \begin{array}{cccc}
 \circ & \circ & \circ & \times \\
 \circ & \circ & \times & \cdot \\
 \circ & \times & \cdot & \cdot \\
 \times & \cdot & \cdot & \cdot
 \end{array}$$

Then in the positions of  $w$  corresponding to these four rows one finds a pattern 3412, 4312, 3421, or 4321.  $\square$

## 7. MULTIPLICITY BOUNDED PERMUTATIONS

We will say a permutation  $w$  is *multiplicity free* provided all nonzero coefficients of the Stanley symmetric function  $F_w$  are 1. See A224287 in the OEIS for the number of multiplicity free permutations in  $S_n$  as a function of  $n$ . By Corollary 4.4, we know the multiplicity free permutations respect pattern containment in the classical sense. We discuss a new type of pattern containment which these permutations also respect using the code of a permutation. We follow up with another variation on the theme of bounding the multiplicities in a Stanley symmetric function which generalize vexillary permutations.

**Lemma 7.1.** *Every 3-vexillary permutation is multiplicity free.*

*Proof.* Apply Lemma 3.11 to  $D(w)$ .  $\square$

The following conjecture has been tested through  $S_{12}$  and one direction follows from Corollary 4.4. For the minimal list of 189 patterns up to  $S_{11}$ , see

<http://www.math.washington.edu/~billey/papers/k.vex.html>.

**Conjecture 3.** *The set of multiplicity free permutations is closed under taking patterns and the minimal patterns all occur in  $S_n$  for  $n \leq 11$ .*

Recall the inversion set of  $w \in S_n$  is

$$\text{Inv}(w) = \{(i, j) : 1 \leq i < j \leq n \text{ and } w_i > w_j\}.$$

The *code* of  $w$  is the vector  $\text{code}(w) = (c_1, \dots, c_n)$  such that  $c_k$  is the number of inversions  $(k, j)$  for any  $k < j \leq n$ . Equivalently,  $c_k$  is the number of cells on row  $k$  of  $D(w)$ . An inverse operation  $\text{code}^{-1}(c_1, \dots, c_n)$  is obtained by multiplying out the reduced expression  $(s_{c_1} \dots s_2 s_1) \cdot (s_{c_2+1} \dots s_3 s_2) \cdots (s_{c_n+n-1} \dots s_n)$  where each factor is a consecutive decreasing string of adjacent transpositions. Adding additional zeros at the beginning or the end of the code will not change the corresponding Stanley symmetric function. Furthermore, for every vector of nonnegative integers there exists a permutation with this vector as its code plus possibly some additional terminal 0's.

For example,  $\text{code}^{-1}(3, 0, 5, 1) = (s_3 s_2 s_1) \cdot (s_7 s_6 s_5 s_4 s_3) \cdot (s_4) = 41832567$  and  $\text{code}(41832567) = (3, 0, 5, 1, 0, 0, 0, 0)$ .

**Definition 7.2.** We will say a permutation  $w$  contains a permutation  $v$  as a *simple code pattern* provided  $\text{code}(w) = (c_1, \dots, c_n)$ , there exists an  $i$  such that  $c_i = 0$ , and  $\text{code}^{-1}(c_1, \dots, \widehat{c_i}, \dots, c_n) = v$ . Say  $w$  contains  $v$  as a *code pattern* provided there exists a sequence of permutations  $u^{(1)}, \dots, u^{(k)}$  such that  $w = u^{(1)}$ ,  $v = u^{(k)}$  and each  $u^{(i)}$  contains  $u^{(i+1)}$  as a simple code pattern. In this case,  $|D(v)| = |D(w)|$ .

**Lemma 7.3.** *If  $w$  contains  $v$  as a code pattern, then  $S^{D(v)} \hookrightarrow S^{D(w)}$  as a submodule and  $F_w - F_v$  is Schur positive.*

*Proof.* Without loss of generality, assume that  $w \in S_n$  contains  $v \in S_n$  as a simple code pattern, and the code of  $v$  is obtained from the code of  $w$  by removing  $c_k = 0$  and adding a zero at the end. Since  $c_k = 0$ ,  $w(k) = \min\{w(k), w(k+1), \dots, w(n)\}$ . Let  $D$  be  $D(w)$  with the empty row  $k$  removed, so  $S^D \simeq S^{D(w)}$ .

Recall that the code of a permutation is given by the number of elements in the diagram on each row. Going from a code vector to the corresponding diagram is easy. Starting at the first row, fill in the appropriate number of cells left justified. Place an  $\times$  in the next position and cross out everything below and to its right. For the next row, starting from the leftmost available position that hasn't already been crossed out, greedily place the appropriate number of cells moving left to right. Once the cells are placed in the row, put an  $\times$  in the next available position and cross out everything below and to the right of the  $\times$ . Continue until only fixed points are added to the permutation. Thus, the first  $k-1$  rows and  $w(k)-1$  columns of  $D$  and  $D(v)$  are identical since the codes of  $v, w$  agree in the first  $k-1$  positions.

It remains to show that there exists a sequence of James-Peel moves taking  $D$  to  $D(v)$  which only modifies cells southeast of  $(k, w(k))$ . Let  $j_1 < j_2 < \dots < j_a$  be the occupied columns of  $D(w)$  southeast of  $(k, w(k))$ . Let  $j_0 = w(k)$ . Observe that  $D(w)$  is empty in column  $j_0$  below row  $k$  but may contain cells above row  $k$ . We claim that for  $i > k$  and  $1 \leq l \leq a$ ,  $(i, j_l) \in D(w)$  if and only if  $(i, j_{l-1}) \in D(v)$  by construction of the diagram from the code. So we can shift the occupied columns of  $D(w)$  southeast of  $(k, w(k))$  over left by applying  $C_{j_0 \rightarrow j_1}$  to  $D$  and then applying  $C_{j_1 \rightarrow j_2}$ , etc. Furthermore, for  $i < k$  if  $(i, j_l) \in D$  then  $(i, j_{l-1}) \in D$  and  $D$  and  $D(v)$  agree above row  $k$ , so applying each  $C_{j_l \rightarrow j_{l-1}}$  to  $D$  does not change any cells above row  $k$ . Thus,

$$D(v) = C_{j_a \rightarrow j_{a-1}} \cdots C_{j_2 \rightarrow j_1} C_{j_1 \rightarrow j_0} D.$$

We conclude that  $S^{D(v)} \hookrightarrow S^{D(w)}$  by Lemma 3.13.  $\square$

**Corollary 7.4.** *Assume  $w$  contains  $v$  as a code pattern. If  $w$  is multiplicity free, then so is  $v$ .*

Next we generalize multiplicity free permutations to a filtration of permutations.

**Definition 7.5.** A permutation  $w$  is  $k$ -multiplicity bounded provided each  $a_{w\lambda} \leq k$  in the expansion  $F_w = \sum_{\lambda} a_{w\lambda} s_{\lambda}$ . Thus, 1-multiplicity bounded is the same as multiplicity free.

For each  $k \geq 1$ , the set of all  $k$ -multiplicity bounded permutations respects pattern containment by Corollary 4.4. If one could bound the size of the minimal patterns which are not  $k$ -multiplicity bounded, then one would prove the following conjecture.

**Conjecture 4.** *The  $k$ -multiplicity-bounded permutations are defined by avoiding a finite set of permutation patterns.*

## 8. FUTURE WORK

We were led to Theorem 1.1 by trying to study pattern containment for diagrams. In particular, we observed in experiments that the conclusion of Corollary 3.19

holds for arbitrary diagrams and subdiagrams. Is this always true? Corollary 3.19 holds when the subdiagram is (equivalent to) a permutation diagram, a skew shape, or a column-convex diagram, since these diagrams all admit complete James-Peel trees. The algorithm given by Reiner and Shimozono in [26] for decomposing Specht modules shows that the conclusion of Corollary 3.19 also holds when  $D$  is percent-avoiding and  $D' = D \cap \{i : a \leq i \leq b\} \times \{j : c \leq j \leq d\}$  for some  $a, b, c, d$ .

We have no simpler characterizations of the lists of patterns arising from Corollary 5.11 and Theorems 5.12 and 5.13. One necessary condition for  $w$  to be non- $k$ -vexillary but contain only  $k$ -vexillary patterns is that every  $w(i)$  participates in some 2143 pattern. Otherwise, the  $i$ th row and  $w(i)$ th column of  $D(w)$  are contained in or contain every other row and column, and so they do not participate in the James-Peel moves of  $RJP(w)$ . This is far from sufficient, however. Magnusson and Úlfarsson [22] have developed an algorithm for characterizing sets of permutations in terms of avoiding mesh patterns, but this algorithm does not seem to simplify our patterns appreciably. One might try even more general notions of patterns, such as marked mesh patterns. Bridget Tenner has noted that some 2-vexillary patterns do collapse. In these cases though, the algorithms for detecting pattern containment require checking for the original patterns.

In [3], vexillary elements of types  $B, C, D$  in the hyperoctahedral group are defined as those whose Stanley symmetric function is equal to a single Schur  $P$ - or  $Q$ -function ( $P$  in types  $B, D$ , and  $Q$  in type  $C$ ), and it is shown that the vexillary elements are again characterized by avoiding a finite set of patterns. Computer calculations show that Corollary 4.3 with  $k = 2$  holds in  $B_9$  for types  $B, C$  and in  $D_8$ ; moreover, the 2-vexillary patterns in  $B_9$  of types  $B, C$  are characterized by avoiding sets of patterns in  $B_3 \cup \cdots \cup B_8$ . The main obstacle to extending our proofs to these other root systems is the apparent lack of an analogue of the Specht module of a diagram. In a recent preprint [1], Fulton and Anderson give a different variation on vexillary permutations in types  $B, C, D$ , and one might ask if there is a reasonable notion of  $k$ -vexillary in their setting.

Klein, Lewis and Morales have recently defined another generalization of vexillary permutations. For  $w \in S_n$ , let  $D(w)$  be its permutation diagram. It is shown in [13], that the rows and columns of  $D(w)$  can be rearranged to form the complement of a skew shape if and only if  $w$  avoids 9 patterns. They call these *skew vexillary* permutation. Under what conditions can the rows and columns of an arbitrary diagram be rearranged into a skew shape or the complement of a skew shape?

#### ACKNOWLEDGMENTS

We would like to thank Dave Anderson, Andrew Berget, Alain Lascoux, Ricky Liu, Aaron Pihlman, Austin Roberts, Mark Shimozono, Bridget Tenner, and Henning Úlfarsson for helpful discussions, and Eric Peterson for the term “bushy”.

#### REFERENCES

- [1] David Anderson and William Fulton. Degeneracy loci, pfaffians, and vexillary signed permutations in types  $B$ ,  $C$ , and  $D$ . arXiv:1210.2066v1 [math.AG], 2012.
- [2] Sara Billey, William Jockusch, and Richard P. Stanley. Some combinatorial properties of Schubert polynomials. *Journal of Algebraic Combinatorics*, 2:345–374, 1993.
- [3] Sara Billey and Tao Kai Lam. Vexillary elements in the hyperoctahedral group. *Journal of Algebraic Combinatorics*, 8:139–152, 1998.

- [4] Anders Claesson, Vít Jelínek, and Einar Steingrímsson. Upper bounds for the Stanley–Wilf limit of 1324 and other layered patterns. *Journal of Combinatorial Theory, Series A*, 119:1680–1691, 2012.
- [5] Andrew Crites, Greta Panova, and Gregory S. Warrington. Shape and pattern containment of separable permutations. arXiv:1011.5491v2 [math.CO], 2011.
- [6] Paul Edelman and Curtis Greene. Balanced tableaux. *Advances in Mathematics*, 1:42–99, 1987.
- [7] Sergi Elizalde. The X-class and Almost-Increasing Permutations. *Annals of Combinatorics*, 15(1):51–68, 2011.
- [8] Sergey Fomin, Curtis Greene, Victor Reiner, and Mark Shimozono. Balanced labellings and Schubert polynomials. *European Journal of Combinatorics*, 18(4):373–389, 1997.
- [9] William Fulton. *Intersection Theory*. Springer-Verlag, New York, 1984.
- [10] William Fulton. Flags, Schubert polynomials, degeneracy loci, and determinantal formulas. *Duke Mathematical Journal*, 65:381–420, 1992.
- [11] William Fulton. *Young Tableaux: With Applications to Representation Theory and Geometry*. Cambridge University Press, 1997.
- [12] G.D. James and M.H. Peel. Specht series for skew representations of symmetric groups. *Journal of Algebra*, 56:343–364, 1979.
- [13] Aaron J. Klein, Joel Brewster Lewis, and Alejandro H. Morales. Counting matrices over finite fields with support on skew Young diagrams and complements of Rothe diagrams. arXiv:1203.5804 [math.CO], 2012.
- [14] Witold Kraszkiewicz. Reduced decompositions in Weyl groups. *European Journal of Combinatorics*, 16:293–313, 1995.
- [15] Alain Lascoux and Marcel-Paul Schützenberger. Polynômes de Schubert. *Comptes Rendus des Séances de l’Académie des Sciences. Série I. Mathématique*, 294:447–450, 1982.
- [16] Alain Lascoux and Marcel-Paul Schützenberger. Structure de Hopf de l’anneau de cohomologie et de l’anneau de Grothendieck d’une variété de drapeaux. *Comptes Rendus des Séances de l’Académie des Sciences. Série I. Mathématique*, 295:629–633, 1982.
- [17] Alain Lascoux and Marcel-Paul Schützenberger. Schubert polynomials and the Littlewood–Richardson rule. *Letters in Mathematical Physics*, 10:111–124, 1985.
- [18] David Little. Combinatorial aspects of the Lascoux–Schützenberger tree. *Advances in Mathematics*, 174:236–253, 2003.
- [19] Ricky Liu. Matching polytopes and Specht modules. *Transactions of the American Mathematical Society*, 364:1089–1107, 2009.
- [20] Ricky Liu. *Specht Modules and Schubert Varieties for General Diagrams*. PhD thesis, Massachusetts Institute of Technology, 2010.
- [21] Ian G. Macdonald. *Notes on Schubert Polynomials*, volume 6. Publications du LACIM, Université du Québec à Montréal, 1991.
- [22] Hjalti Magnússon and Henning Ulfarsson. Algorithms for discovering and proving theorems about permutation patterns. arXiv:1211.7110 [math.CO], 2012.
- [23] Laurent Manivel. *Fonctions symétriques, polynômes de Schubert et lieux de dégénérescence*. Société Mathématique de France, 1998.
- [24] Victor Reiner and Mark Shimozono. Plactification. *Journal of Algebraic Combinatorics*, 4:331–351, 1995.
- [25] Victor Reiner and Mark Shimozono. Specht series for column-convex diagrams. *Journal of Algebra*, 174:489–522, 1995.
- [26] Victor Reiner and Mark Shimozono. Percentage-avoiding, northwest shapes, and peelable tableaux. *Journal of Combinatorial Theory, Series A*, 82:1–73, 1998.
- [27] Victor Reiner, Alexander Woo, and Alexander Yong. Presenting the cohomology of a Schubert variety. *Transactions of the American Mathematical Society*, 363:521–543, 2011.
- [28] Heinrich Rothe. Ueber Permutationen, in Beziehung auf die Stellen ihrer Elemente. Anwendung der daraus abgeleiteten Satze auf das Eliminationsproblem. In Carl Hindenburg, editor, *Sammlung Combinatorisch-Analytischer Abhandlungen*, pages 263–305. Bey G. Fleischer dem jüngern, 1800.
- [29] Bruce Sagan. *The Symmetric Group: Representations, Combinatorial Algorithms, and Symmetric Functions*. Springer-Verlag, 2001.
- [30] Richard P. Stanley. On the number of reduced decompositions of elements of Coxeter groups. *European Journal of Combinatorics*, 5:359–372, 1984.

- [31] John R. Stembridge. Multiplicity-free products of Schur functions. *Annals of Combinatorics*, 5(2):113–121, 2001.
- [32] Bridget Eileen Tenner. Reduced decompositions and permutation patterns. *Journal of Algebraic Combinatorics*, 24:263–284, 2006.
- [33] Hugh Thomas and Alexander Yong. Multiplicity-free Schubert calculus. *Canadian Mathematical Bulletin. Bulletin Canadien de Mathématiques*, 53(1):171–186, 2010.